DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ORWELL VT-73 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	3.149	E	W1-6	48	24								1	X															
		F	W1-6	48	24								1																
		E	W1-6R	48	24			8.00																			X		
		F	W1-6L	48	24			8.00																			X		
WB	3.121	G	VR-017	24	30								1	X													EXISTING POST WAS DAMAGED			
		G	VR-017	24	30			5.00								I		13.25 X								OLD SAWMILL RD (TH-25)		9	
WB	3.121	E	W1-6	48	24								1	X															
		E	W1-6R	48	24			8.00																			X		
WB	3.120	E/F	D3-1	UNK.	UNK.								1		X														
		E/F	D3-1	62	12			5.17								2		11.0 X 11.25								OLD SAWMILL RD (TH-25)		11	
WB	3.110	H	R1-1	30	30		STOP MM PLAQUE				I	I	1 I	X													MM PLAQUE SALVAGED EXISTING POST WAS DAMAGED			
		H	R1-1	30	30			6.25								I		13.25 X								OLD SAWMILL RD (TH-25)	X		
WB	3.091	F	VD-062AL	72	16		BUSINESS SIGN			1				X															
WB	3.031	G	VR-017	24	30								1	X													EXISTING POST WAS DAMAGED			
		G	VR-017	24	30			5.00								I		14.25 X								GRISWOLD LN (TH-23); MOUNT 30' CLOSER TO ROUTE 73		9	
SIGN SUMMARY SHEET							SHEET TOTALS	45.42	0.00	1	I ~~0~~	I ~~0~~	~~8~~ 7	0	0	~~5~~ 2		63.0 ~~30.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	407.4	0.0	1	3	3	73	0	0	45		675.0		0	0.0								

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(47)**
FILE NAME: **z12c534TSS.xlsm**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **B. TOOTHAKER**
PLOT DATE: **9/12/2014**
DRAWN BY: **B. TOOTHAKER**
CHECKED **K. KERN**
ORWELL WB SHEET 3
SHEET **24** OF **107**