DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ORWELL VT-73 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	0.717	F	R2-1	24	30		SPEED LIMIT 35						1		X													
WB	0.694	F	VD-018	30	18		VILLAGE SIGN - ORWELL JCT 22A						1		X													
			R2-1	30	36			7.50								1		13.75 X								X	
WB	0.664	F	W1-1L	30	30		LEFT TURN						1		X													
		F	W13-1	18	18		20 MPH						1															
WB	0.620	F	W1-8	18	24			3.00								1		11.75 X									INSTALL 26 FT EAST OF EXISTING	X	
		E	W1-8	18	24			3.00																			X	
WB	0.601	F	W1-8	18	24		CHEVRON						1		X													
		E	W1-8	18	24		CHEVRON						1															
WB	0.582	F	W1-8	18	24								1	X														
		E	W1-8	18	24								1															
		F	W1-8	18	24			3.00																			X	
		E	W1-8	18	24			3.00							I			12.0 X							EXISTING POST WAS DAMAGED	X	
WB	0.572	F	W1-8R	18	24								1		X													
		F	W1-8L	18	24			3.00								1		10.25 X								INSTALL 69 FT WEST OF EXISTING	X	
SIGN SUMMARY SHEET							SHEET TOTALS	22.50	0.00	0	0	0	9	0	0	4 ~~3~~		47.75 ~~45.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	407.4	0.0	1	3	3	73	0	0	45		675.0		0			0.0					

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(47)**
FILE NAME: **z12c534TSS.xlsm**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **B. TOOTHAKER**
PLOT DATE: **9/12/2014**
DRAWN BY: **B. TOOTHAKER**
CHECKED **K. KERN**
ORWELL WB SHEET 6
SHEET **27** OF **107**