DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ORWELL VT-73 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		E	W1-8L	18	24			3.00																				
WB	0.457	F	R2-1	24	30								1	X												EXISTING POST WAS DAMAGED		
		F	R2-1	24	30			5.00								1		13.0 X								X	
WB	0.411	F	S1-1	30	30								1		X													
		F	S1-1	36	36	FYG		9.00								2		13.5 X 13.75								X	
		F	S4-3P	24	8	FYG		1.33																		X	
WB	0.375	G	R2-1	24	30		SPEED LIMIT 25				1	1	1		X											SALVAGE AND MOUNT BELOW LEGAL LOAD SIGN		
		G	VR-017	24	30			5.00								1			15.75 X							N ORWELL RD (TH-1); MOUNT AT LOCATION OF EXISTING SPEED LIMIT 25		9
WB	0.365	H	R1-1	30	30		MM PLAQUE						1 1		X													
		E\F	D3-1	UNK.	UNK.		N ORWELL RD						1															
		H	R1-1	30	30			6.25								1		13.25 X								N ORWELL RD (TH-1)	X	
WB	0.364	E\F	D3-1	42	12			3.50								1		11.0 X								N ORWELL RD (TH-1); FIELD LOCATE FOR VISIBILITY FROM VT73		11
WB	0.358	F	VR-004A	24	30		YIELD TO PEDESTRIANS IN CROSSWALK SYMBOL						1		~~X~~													
		E	VR-004A	24	30		YIELD TO PEDESTRIANS IN CROSSWALK SYMBOL						1															
		F	S1-1	36	36	FYG		9.00								2		14.0 X 14.0								X	
SIGN SUMMARY SHEET							SHEET TOTALS	42.08	0.00	0	1	1	~~8~~ 7	0	0	~~8~~ 7		~~108.25~~ 105.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	407.4	0.0	1	3	3	73	0	0	45		675.0		0	0.0							

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(47)**

FILE NAME: **z12c534TSS.xlsm** PLOT DATE: **9/12/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **B. TOOTHAKER**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
ORWELL WB SHEET 7 SHEET **28** OF **107**