DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SHOREHAM VT-74 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	VR-048	24	30		STATE LAW STOP FOR SCHOOL BUS FLASHING RED LIGHTS						1																
		A	VR-039	24	18		STATE HIGHWAY BEGINS MM PLAQUE 0000				I		1 I																
		A	VR-039	24	18		STATE HIGHWAY BEGINS	3.00				I				1		11.75 X										9	
EB	0.006	A	VD-421A	60	48								1		X											(2) SOIL BEARING SLIP BASES			
		A	VD-421A	60	48		Welcome To VERMONT THE GREEN MOUNTAIN STATE	20.00								2			9.25 X 9.25							INSTALL FACING TRAFFIC EXITING FERRY		6	
EB	0.075	A	VR-114R	48	60		STATE OF VERMONT SPEED LIMIT 50 UNLESS OTHERWISE POSTED						1	X															
		A	VW-362P	24	12	FY	STATE LAW	2.00																				9	
		A	R2-1	24	30		SPEED LIMIT 50	5.00																			X		
		A	R2-5P	24	18		UNLESS OTHERWISE POSTED	3.00																			X		
EB	0.186	A	VR-023B	24	30		MM PLAQUE 0020				I		1 I		X														
		A	VR-023B	24	30		$500 FINE THROWING TRASH ON HIGHWAYS AND STREAMS	5.00				I				1		14.25 X										9	
EB	0.246	A	UNK.	UNK.	UNK.		BUCKLE UP IT'S THE LAW						1		X														
		A	VR-601	36	36		SAFETY BELTS REQUIRED	9.00								2		15.0 X 15.25										9	
EB	0.333	A	UNK.	72	16		BUSINESS SIGN			1				X												REQUIRES VEGETATION CLEARING			
EB	0.390	A	M2-1	21	15		ROUTE MARKER ASSEMBLY						1		X														
							SHEET TOTALS	47.00	0.00	1	2 ~~0~~	2 ~~0~~	9 ~~7~~	0	0	6		74.75 ~~90.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	771.0	0.0	1	2	2	137	0	0	88		1320.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE-SOUTHWEST
PROJECT NUMBER: STPG SIGN(47)

FILE NAME: z12c534TSS.xlsm
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
SHOREHAM EB SHEET 2

PLOT DATE: 9/12/2014
DRAWN BY: B. TOOTHAKER
CHECKED: K. KERN