DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.88	SQUARE STEEL (IN) (LB / FT) 2.42	SQUARE STEEL (IN) (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SHOREHAM VT-74 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		13.75 X											
EB	1.145	B	W1-6	48	24								1		X														
		B	W1-6R	48	24			8.00								2		13.75 X 13.75										X		
EB	1.151	D	R1-1	30	30		STOP	6.25								1		14.25 X									BARNUM HILL RD (TH-41)	X		
EB	1.367	A	W1-2MR	30	30		MODIFIED RIGHT CURVE						1		X														
EB	1.414	A	W1-10R	36	36			9.00								2		14.25 X 14.25									INSTALL 250 FT EAST OF EXISTING	X		
		A	W13-1P	18	18		45 M.P.H.	2.25																				X		
EB	1.483	A	R2-1	24	30		SPEED LIMIT 50	5.00								1		14.25 X									INSTALL 100 FT EAST OF SMITH ST.	X		
EB	2.526	A	W13-1	18	18		25 MPH MM PLAQUE 0254						1 1		X														
		A	W1-1ML	30	30		MODIFIED LEFT TURN						1																
EB	2.602	A	W1-1ML	36	36			9.00								2		14.75 X 14.5									INSTALL400 FT EAST OF EXISTING	X		
		A	W13-1P	18	18		30 M.P.H.	2.25																				X		
EB	2.670	C	VR-017	24	30								1	X															
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																					9	
EB	2.671	A	W1-6	48	24								1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	51.75	0.00	0	0	0	7 ~~6~~	0	0	9		~~127.5~~ ~~135.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	771.0	0.0	1	2	2	137	0	0	88		1320.0		0		0.0							

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(47)**
FILE NAME: **z12c534TSS.xlsm**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **B. TOOTHAKER**
SHOREHAM EB SHEET 7
PLOT DATE: **9/12/2014**
DRAWN BY: **B. TOOTHAKER**
CHECKED **K. KERN**
SHEET **43** OF **107**