DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SHOREHAM VT-74 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M1-5	24	24	GRN/ WHT		4.00																					E-136b
		A	M6-1	21	15	GRN/ WHT		2.19																					E-136b
EB	5.234	A	OM1-1	18	18								1		X														
		A	OM-3R	12	36			3.00								1		10.25 X								INSTALL AT ROADWAY EDGE OF ISLAND	X		
EB	5.236	A	R1-1	30	30		MM PLAQUE 0311				1		1		X														
		A	R1-1	30	30			6.25				1				1		12.5 X									X		
EB	5.244	GHOST SECTION OVERLAP WITH VT-22a, GHOST SECTION NOT INCLUDED AS PART OF THIS PROJECT																											
EB	5.253	B	R1-1	30	30			6.25								1		13.25 X								INSTALL DIRECTLY ACROSS FROM WB STOP	X		
EB	5.275	A	M3-2	24	12		ROUTE MARKER ASSEMBLY						1	X															
		A	M1-5	24	24								1																
		A	M3-2	24	12	GRN/ WHT		2.00																					E-136b
		A	M1-5	24	24	GRN/ WHT		4.00																					E-136b
EB	5.306	A	D2-1	72	10		D-BOARD MARKER ASSEMBLY						1	X															
		A	D2-1	72	10								1																
		A	VD2-1	72	12			6.00																				8	
SIGN SUMMARY SHEET							SHEET TOTALS	33.69	0.00	0	1 ~~0~~	1 ~~0~~	7 ~~6~~	0	0	3		36.0 ~~45.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	771.0	0.0	1	2	2	137	0	0	88		1320.0		0		0.0							

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(47)**

FILE NAME: **z12c534TSS.xlsm**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **B. TOOTHAKER**
SHOREHAM EB SHEET 16

PLOT DATE: **9/12/2014**
DRAWN BY: **B. TOOTHAKER**
CHECKED **K. KERN**
SHEET **52** OF **107**