DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SHOREHAM VT-74 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	8.365	A	W1-2R	30	30		RIGHT CURVE						1		X													
EB	8.365	A	W13-1	18	18		25 MPH						1															
EB	8.474	A	W1-10cR	36	36			9.00			2	2	2			2		15.75 X 15.25								INSTALL ACROSS ROAD FROM MIDSPAN OF WB TOWN HIGHWAY INTERSECTIONS	X		
		A	W13-1P	18	18			2.25																			INSTALL ON LEFT POST	X		
EB	8.831	C	VR-017	24	30			5.00					1	X													QUIET VALLEY RD (TH-19)		9	
EB	8.838	D	R1-1	30	30								1	X														
		A/B	D3-1	UNK.	UNK.		QUIET VALLEY RD (TH-19)						1															
		D	R1-1	30	30			6.25																			QUIET VALLEY RD (TH-19)	X		
EB	8.838	A/B	D3-1	64	12			5.33								2		11.0 X 10.75								QUIET VALLEY RD (TH-19); FIELD LOCATE FOR VISIBILITY FROM VT74		12	
EB	9.577	A	W1-2L	30	30		LEFT CURVE MM PLAQUE 0957						1 1		X													
		A	W13-1	18	18		35 MPH						1															
EB	9.646	A	VW-054L	30	30		HIDDEN DRIVE LEFT						1	X														
		A	VW-054L	30	30			6.25																				X		
EB	9.688	A	W1-2L	30	30			6.25								1		16.25 X								INSTALL 220 FT EAST OF HIDDEN DRIVE LEFT	X		
SIGN SUMMARY SHEET							SHEET TOTALS	40.33	0.00	0	~~2~~ 0	~~2~~ 0	~~11~~ 8	0	0	5		~~69.0~~ 75.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	771.0	0.0	1	2	2	137	0	0	88		1320.0		0		0.0							

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(47)**
FILE NAME: **z12c534TSS.xlsm** PLOT DATE: **9/12/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **B. TOOTHAKER**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
SHOREHAM EB SHEET 19 SHEET **55** OF **107**