DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SHOREHAM VT-74 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	4.994	H	R1-1	30	30								1		X														
							MM PLAQUE 0498				I		I																
		E/F	D3-1	26	12		Inn Rd STOP	2.17				I				1		13.25 X									12	
		H	R1-1	30	30			6.25																		INN RD (TH-52)	X		
WB	4.963	F	W16-9	24	10								1	X															
		F	S1-1	36	36								1													(I) POST BENT (I) POST RETAINED			
		F	S1-1	36	36	FYG	 AHEAD	9.00								1		12.75 X									X		
		F	W16-9P	24	12	FYG		2.00																			X		
WB	4.907	F	W1-1ML	30	30		MODIFIED LEFT TURN						1	X															
		F	W13-1	18	18		25 MPH						1																
		F	R2-1	24	30		SPEED LIMIT 30	5.00																			X		
WB	4.836	F	W1-1ML	36	36			9.00								~~2~~ 1		15.0 X 14.5								INSTALL DIRECTLY ACROSS FROM EB SCHOOL WARNING ASSEMBLY		9	
WB	4.814	F	M3-4	24	12		WEST						1		X														
		F	M1-5A	24	24		ROUTE 74						1																
		F	M6-1	21	15		<--- LEFT						1																
WB	4.808	E	W1-6	48	24								1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	33.42	0.00	0	~~I~~ 0	~~I~~ 0	~~10~~ 9	0	0	2		~~55.5~~ 30.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	660.5	0.0	0	2	2	107	0	0	80		1200.0		0			0.0					

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(47)**
FILE NAME: **z12c534TSS.xlsm**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **B. TOOTHAKER**
PLOT DATE: **9/15/2014**
DRAWN BY: **B. TOOTHAKER**
CHECKED **K. KERN**
SHOREHAM WB SHEET 8
SHEET **64** OF **107**