| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **BRIDPORT VT-125 EB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| | | A | M1-5 | 24 | 24 | | | | | | | | ~~1~~ | | | | | | | | | | | | | | | | |
| | | A | M2-1 | 21 | 15 | GRN/ WHT | | 2.19 | | | | | | | | 1 | | 14.0 X | | | | | | | | | | | E-136b |
| | | A | M1-5 | 24 | 24 | GRN/ WHT | | 4.00 | | | | | | | | | | | | | | | | | | | | | E-136b |
| EB | 5.114 | A | W3-1 | 36 | 36 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | W3-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | 9.25 X | | | | | | | | | X | | |
| EB | 5.146 | A | D1-1A | 72 | 10 | | D-BOARD ASSEMBLY | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | D1-1A | 72 | 10 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | D1-1A | 72 | 10 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | D1-1A | 72 | 10 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | VD1-1a | 72 | 12 | | | 6.00 | | | | | | | | 2 | | | 10.75 X 10.25 | | | | | | | (2) SOIL BEARING SLIP BASES | | 8 | |
| | | A | VD1-1a | 72 | 12 | | ← Addison 7 | 6.00 | | | | | | | | | | | | | | | | | | | | 8 | |
| | | A | VD1-1a | 72 | 12 | | ← Vergennes 14<br>Middlebury 9 → | 6.00 | | | | | | | | | | | | | | | | | | | | 8 | |
| | | A | VD1-1a | 72 | 12 | | Fair Haven 29 → | 6.00 | | | | | | | | | | | | | | | | | | | | 8 | |
| EB | 5.186 | A | M6-1 | 21 | 15 | | ROUTE MARKER ASSEMBLY | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | M1-5 | 30 | 24 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | | | | | | SHEET TOTALS | 36.44 | 0.00 | 0 | 0 | 0 | ~~6~~ 7 | 0 | 0 | 4 | | 44.25 ~~60.0~~ | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | EA | LB | LB | LB | LB | | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 250.6 | 0.0 | 9 | 1 | 1 | 49 | 0 | 0 | 42 | | 630.0 | | 0 | | 0.0 | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE-SOUTHWEST
PROJECT NUMBER: STPG SIGN(47)

FILE NAME: z12c534TSS.xlsm
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
BRIDPORT EB SHEET 4

PLOT DATE: 9/15/2014
DRAWN BY: B. TOOTHAKER
CHECKED: K. KERN