DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CORNWALL VT-125 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	4.102	F	VW-092	36	36								1		X														
		F	VW-092	36	36		UNSAFE TO PASS	9.00								2		14.75 X 14.75										X	
WB	3.512	F	R2-5A	24	30		REDUCED SPEED AHEAD						1		X														
WB	3.434	F	W3-5	36	36		SPEED LIMIT 40	9.00								2		15.0 X 15.5									INSTALL 500 FT EAST OF NEW SPEED LIMIT SIGN	X		
WB	3.350	F	R2-1	24	30								1		X														
		F	R2-1	30	36		SPEED LIMIT 40	7.50								1		14.0 X										X	
WB	3.312	F	W2-1	30	30			6.25								1		15.75 X									INSTALL 200 FT WEST OF SPEED LIMIT 40	X		
WB	3.267	G	VR-017	24	30		SPEED LIMIT 40				I	I	1		X														
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		16.0 X									JAMES RD (TH-2)		9	
WB	3.267	H	R1-1	30	30								1	X															
		H	R1-1	30	30		STOP	6.25																			JAMES RD (TH-2)	X		
WB	3.260	E/F	D3-1	UNK.	UNK.								1	X															
		H	R1-1	30	30								1																
		E/F	D3-1	40	12		James Rd	3.33																			JAMES RD (TH-2); MOUNT ON STOP SIGN WITH BRACKET		13	
		H	R1-1	30	30		STOP	6.25																			JAMES RD (TH-2)	X		
SIGN SUMMARY SHEET							SHEET TOTALS	52.58	0.00	0	I 0	I 0	7	0	0	7		105.75 ~~105.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	174.8	0.0	3	1	1	33	0	0	28		420.0		0	0.0								

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(47)**
FILE NAME: **z12c534TSS.xlsm** PLOT DATE: **9/15/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **B. TOOTHAKER**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
CORNWALL WB SHEET 1 SHEET **102** OF **107**