

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES						TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
EMPLOYEE TRAINEESHIP	ROADWAY	EROSION CONTROL	FULL C.E. ITEM	BOAT LAUNCH	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
	1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10					
	5800			3000	8800		CY	COMMON EXCAVATION	203.15	88				
				1680	1680		CY	CHANNEL EXCAVATION OF EARTH	203.25					
	325				325		CY	EARTH BORROW	203.30	29				
				3000	3000		CY	GRANULAR BORROW	203.32					
				30	30		CY	GRAVEL BACKFILL FOR SLOPE STABILIZATION	203.35					
	25				25		CY	TRENCH EXCAVATION OF EARTH	204.20					
	1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.				
				300	300		CY	STRUCTURE EXCAVATION	204.25					
	70				70		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	3.86				
				1	1		LS	COFFERDAM	208.40					
	3400				3400		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	199				
	1200				1200		CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	100				
	75			105	180		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35					
	30				30		TON	AGGREGATE SHOULDERS	402.12	3				
	50				50		CWT	EMULSIFIED ASPHALT	404.65	12				
	1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	EST.				
	675				675		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	21				
	1				1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	EST.				
				5925	5925		LB	REINFORCING STEEL, LEVEL 1	507.11					
				50	50		LF	DRILLING AND GROUTING DOWELS	507.16					
	1				1		EACH	REMOVAL OF STRUCTURE (FERRY ACCESS ABUTMENT)	529.15					
				45	45		CY	REMOVAL OF CONCRETE OR MASONRY	529.25					
				80	80		CY	CONCRETE, CLASS A	541.22					
				3	3		CY	CONCRETE, CLASS B	541.25					
	94				94		LF	18" CPEP(SL)	601.2615					

QUANTITY SHEET #1	PROJECT NAME: LAKE CHAMPLAIN SITE RESTORATION
	PROJECT NUMBER: STP 032-118)
	FILE NAME: z12E008...quan_01.dgn
	PLOT DATE: 7/12/2012
PROJECT LEADER: D.E.G.	DRAWN BY: W.G.P.
DESIGNED BY: B.T.H.	CHECKED BY: D.E.G.
DWG. NO.: QU-1	SHEET 6 OF 100

FILE NAME = I:\2012\30\ACAD\DWG\MSTN\z12E008...quan_01.dgn
 DATE/TIME = 7/12/2012
 USER = 4666