STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 5

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (in) | HEIGHT (in) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | SALVAGE | NEW SIGN POSTS NO. OF POSTS | FLANGED CHANNEL lb/ft 1.12 | 2.0 | 3.0 | SQUARE STEEL (in) 1.75 lb/ft 1.88 | 2.0 lb/ft 2.42 | 2.5 lb/ft 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3 | 4.0 lb/ft 1.7 | 4.0 MOD lb/ft 1.7 | TUBULAR STEEL Ø (in) FOUNDATION | 3.0 lb/ft 7.6 | 3.5 lb/ft 9.0 | 4.0 lb/ft 10.8 | 5.0 lb/ft 14.6 | W-SHAPE STEEL FTG. SIZE 24" | 30" | WEIGHT | POST SIZE | SIGN REQUIRED | REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK | SIGN DETAIL DETAIL IN SHS | DETAIL ON DWG. NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| ADDISON: V 12+00. RT | WEST EAST | 1<br>1 | 24<br>24 | 12<br>12 | 2.00<br>2.00 | | | | | A | 2 | | | | | X | | X | | | | | | | | | | | | | | X | SIGN ID CODE M3-4<br>SIGN ID CODE M3-2 | | | E-136B<br>E-136B |
| | VERMONT 17 VERMONT 17 | 1<br>1 | 24<br>24 | 24<br>24 | 4.00<br>4.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE MI-5<br>SIGN ID CODE MI-5 | | | E-136B<br>E-136B |
| | | 1<br>1 | 21<br>21 | 15<br>15 | 2.19<br>2.19 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE M6-IL<br>SIGN ID CODE M6-IR | | | E-136B<br>E-136B |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| V 12+21.0, LT | EAST | 1 | 24 | 12 | 2.00 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE M3-2 | | | E-136B |
| | VERMONT 125 | 1 | 30 | 24 | 5.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE MI-5 | | | E-136B |
| | | 1 | 12 | 18 | 1.50 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE VD-503 | | | E-131B |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| V 12+25.0, LT | ONE WAY ONE WAY | 1<br>1 | 36<br>36 | 12<br>12 | 3.00<br>3.00 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | BACK-TO-BACK<br>SIGN ID CODE R6-IR<br>SIGN ID CODE R6-IL | X<br>X | | |
| | STOP | 1 | 30 | 30 | 6.25 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE RI-1 | X | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| V 13+07.0, LT | SAFETY BELTS & REQUIRED | 1 | 36 | 36 | 9.00 | | | | | | 2 | | | | | X | | X | | | | | | | | | | | | | | | | | 60 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| V 13+65.0, RT | STOP | 1 | 30 | 30 | 6.25 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE RI-1 | X | | |
| | 0170 0101 0036 | 1 | 6 | 10 | 0.42 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE VD-700 | | | E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| P 10+05.0, RT | ONE WAY ONE WAY | 1<br>1 | 36<br>36 | 12<br>12 | 3.00<br>3.00 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | BACK-TO-BACK<br>SIGN ID CODE R6-IR<br>SIGN ID CODE R6-IL | X<br>X | | |
| | | | | | | | | | | | | LF | LF | LF | LF | LF 112 | LF | | EA. | LB | LB | LB | | LB | LB | LB | LB | | | | | | | | |
| FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE." | | **TOTALS** | SF 58.80 | SF | EA. | SF | | | | | | LF | | | LF 112 | | | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | | | | |

**TRAFFIC SIGN SUMMARY SHEET #5**

PROJECT NAME: LAKE CHAMPLAIN SITE RESTORATION
PROJECT NUMBER: STP 032-1(18)

FILE NAME: zi2E008_tss_05.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: B.T.H.
DWG. NO.: TSS-5

PLOT DATE: 7/12/2012
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 58 OF 100

FILE NAME = U:\2E008\CADD\MSTN\zi2E008_tss_05.dgn
DATE/TIME = 7/12/2012
USER = 4666