STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET SHEET

DIRECTION	MILE MARKER, STATION OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES OR DESIGNATE STATE SIGN CODE	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST. POST RETAIN	EXIST. POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS SHSM BOOK = STANDARD HIGHWAY SIGN & MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM BOOK	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
OPTION ITEMS																												
	STA. 157+61	RT	VD2-1S(L)	72	20		← Ferrisburgh Central School	10.00								2	.	X	.									T-93
	STA. 159+61	RT	W3-3	30	30			6.25								1	.	X	.								X		
	STA. 161+90	RT	VR-922L	36	30			7.50								2	.	X	.									E-145A
	STA. 167+26	LT	VR-922L	36	30			7.50								2	.	X	.									E-145A
	STA. 169+39	LT	W3-3	30	30			6.25								1	.	X	.								X		
	STA. 171+76	LT	VD2-1S(R)	72	20		Ferrisburgh Central School →	10.00								2	.	X	.									T-93
	MAST ARM 2A (US ROUTE 7 NB)		D3-1	90	24		Little Chicago Rd	15.00									.	-	.							SIGN TOO LARGE FOR MAST ARM PROVIDED TO DISTRICT #5 ~~MOUNTED ON MAST ARM~~ ~~BRACKET REQUIRED~~		14	
	MAST ARM 1A (US ROUTE 7 SB)		D3-1	78	24		Middlebrook Rd	13.00									.	-	.							SIGN TOO LARGE FOR MAST ARM PROVIDED TO DISTRICT #5 ~~MOUNTED ON MAST ARM~~ ~~BRACKET REQUIRED~~		14	
	STA 164+14	LT					LITTLE CHICAGO RD	---		x							.	-	.							RETAIN ORIGINAL SIGN AND POSTS			
	STA 165+29	RT					MIDDLEBROOK RD	---		x							.	-	.							RETAIN ORIGINAL SIGN AND POSTS			
																	.	-	.										
																	.	-	.										
																	.	-	.										
																	.	-	.										
																	.	-	.										
																	.	-	.										
																	.	-	.										
																	.	-	.										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

			EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB
			.	.	.	.	.	.		.	150.	.		.	.	.	.
SHEET SUBTOTALS	SF 75.50	SF 0.00	EA 0				EA 0		EA 10	FT 150.00			EA. 0	LB 0.00			

PROJECT NAME:	FERRISBURGH
PROJECT NUMBER:	NHG SGNL(42)
FILE NAME: t13b016frm.dgn	PLOT DATE: 3/2/2016
PROJECT LEADER: I. DEGUTIS	DRAWN BY: I. DEGUTIS
DESIGNED BY: I. DEGUTIS	CHECKED BY: P. COBURN
TRAFFIC SIGN SUMMARY SHEET	SHEET 13 OF 22