

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
								80			80		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
								240			240		HR	FLAGGERS	630.15	EST.			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
								1			1		LS	MOBILIZATION/DEMOLITION	635.11	-			
								1			1		LS	TRAFFIC CONTROL	641.10	-			
								500			500		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	19			
								110			110		LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	2			
								39			39		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-			
								1150			1150		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	4			
									5		5		LB	SEED	651.15	EST.			
									0.3		0.3		TON	HAY MULCH	651.25	EST.			
									10		10		CY	TOPSOIL	651.35	EST.			
								14			14		SF	TRAFFIC SIGNS, TYPE A	675.20	-			
								75			75		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	EST.			
								23			23		EACH	REMOVING SIGNS	675.50	-			
								20			20		EACH	ERECTING SALVAGED SIGNS	675.60	-			
								3			3		EACH	SETTING SALVAGED POSTS	675.61	-			
								1			1		EACH	TRAFFIC CONTROL SIGNAL SYSTEM, INTERSECTION (VT 100 @ I-89 EXIT 10 NB OFF-RAMP)	678.15	-			
								1			1		EACH	TRAFFIC CONTROL SIGNAL SYSTEM, INTERSECTION (VT 100 @ I-89 EXIT 10 SB OFF-RAMP)	678.15	-			
								1330			1330		LF	WRED CONDUIT (2")(PVC)(SCH. 80)	678.23	17			
								3			3		EACH	PULL BOX, STANDARD	678.25	-			
								1			1		EACH	JUNCTION BOX	678.26	-			
								2			2		EACH	BRACKET ARM	679.47	-			
								2			2		EACH	SPECIAL PROVISION (LUMINAIRE, LED)	900.620	-			
								1			1		EACH	SPECIAL PROVISION (REMOVE EXISTING LIGHT POLE)	900.620	-			
								4			4		EACH	SPECIAL PROVISION (SOIL BEARING SLIP BASE)(2 1/2")	900.620	-			
								75			75		LF	SPECIAL PROVISION (HORIZONTAL DIRECTIONAL DRILLING)(12" CASING PIPE)	900.640	-			
								1			1		LS	SPECIAL PROVISION (RETIMING OF SIGNAL CORRIDOR)	900.645	-			

PROJECT NAME: WATERBURY
PROJECT NUMBER: NHG SGNL(43)
FILE NAME: t13b018frm.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: I. DEGUTIS
QUANTITY SHEET
PLOT DATE: 12/31/2013
DRAWN BY: I. DEGUTIS
CHECKED BY: M. LACROIX
SHEET 5 OF 17