

SUBJECT: VERMONT, 34' & 31' MAST ARMS W/12' LUM ARM

FOLDER: VTTRAF FILE: 3431L12

SIGNAL AND SIGN ARM 1

=====

SHAPE	= Round
SPAN LENGTH	= 34.00 FT
BASE O.D.	= 11.50 IN
TAPER	= 0.14 IN/FT
ATTACH. HT. *	= 20.00 FT
ORIENTATION **	= 0 DEGREES
SLOPE AT BASE	= 0 DEGREES
CENTROID LOCATION	
HORIZONTAL	= 15.52 FT
ABOVE ATTACH.	= 0.00 FT
UNBENT LENGTH	= 34.00 FT
MATERIAL-BASE	= S105 - 55 ksi
WEIGHT	= 608 LBS

BASE WELD FATIGUE CATEGORY = Full-Pen / E

ARM 1 SECTIONS

=====

BASE SECTION	
THICKNESS	= 0.1793 IN
LENGTH	= 34.00 FT
YIELD STRENGTH	= 55 KSI

SIGNAL AND SIGN ARM 2

=====

SHAPE	= Round
SPAN LENGTH	= 31.00 FT
BASE O.D.	= 11.00 IN
TAPER	= 0.14 IN/FT
ATTACH. HT. *	= 20.00 FT
ORIENTATION **	= 90 DEGREES
SLOPE AT BASE	= 0 DEGREES
CENTROID LOCATION	
HORIZONTAL	= 14.23 FT
ABOVE ATTACH.	= 0.00 FT
UNBENT LENGTH	= 31.00 FT
MATERIAL-BASE	= S105 - 55 ksi
WEIGHT	= 537 LBS

BASE WELD FATIGUE CATEGORY = Full-Pen / E

ARM 2 SECTIONS

=====

BASE SECTION	
THICKNESS	= 0.1793 IN
LENGTH	= 31.00 FT
YIELD STRENGTH	= 55 KSI

- \* THIS IS HEIGHT OF ATTACHMENT TO POLE ABOVE BOTTOM OF BASE PLATE OR TRANSFORMER BASE. SEE \*\*\* BELOW.
- \*\* ARM ORIENTATIONS ARE ANGLES FROM +X AXIS IN X-Y PLANE. X AND Y AXIES ARE PERPENDICULAR/PARALLEL TO SIDES OF POLE BASE PLATE. SEE \*\*\* BELOW.
- \*\*\* IF ARM IS ATTACHED WITH A CLAMP, HEIGHT AND ORIENTATION MUST NOT BE CHANGED FROM VALUES SHOWN ABOVE WITHOUT CONSULTING VALMONT.