

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								25			25		CY	COMMON EXCAVATION	203.15	5			
								355			355		CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	8			
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
								90			90		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	10			
								0.3			0.3		CWT	EMULSIFIED ASPHALT	404.65	0.05			
								1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
								1			1		MGAL	DUST CONTROL WITH WATER	609.10	EST.			
								270			270		LF	GRANITE SLOPE EDGING	616.20	4			
								100			100		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	15			
								2			2		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
								75			75		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	5			
								320			320		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
								480			480		HR	FLAGGERS	630.15	EST.			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
								1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
								3			3		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
								1450			1450		LF	4 INCH WHITE LINE, WATERBORNE PAINT	646.201	14			
								420			420		LF	4 INCH YELLOW LINE, WATERBORNE PAINT	646.2111	6			
								360			360		LF	8 INCH WHITE LINE, WATERBORNE PAINT	646.221	8			
								80			80		LF	24 INCH STOP BAR, WATERBORNE PAINT	646.261	5			
								2			2		EACH	LETTER OR SYMBOL, WATERBORNE PAINT	646.301	-			
								270			270		LF	PAINTED CURB	646.81	4			
								450			450		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	12			
									20		20		LB	SEED	651.15	3			
									170		170		LB	FERTILIZER	651.18	24			
									0.75		0.75		TON	AGRICULTURAL LIMESTONE	651.20	0.17			
									0.75		0.75		TON	HAY MULCH	651.25	0.17			
								160			160		CY	TOPSOIL	651.35	3			
									1		1		LS	EPSC PLAN	652.10	-			
									10		10		HR	MONITORING EPSC PLAN	652.20	EST.			
									1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
									1440		1440		SY	TEMPORARY EROSION MATTING	653.20	28			
									45		45		CY	VEHICLE TRACKING PAD	653.35	6			
									1		1		EACH	INLET PROTECTION DEVICE, TYPE II	653.41	-			
									1400		1400		LF	BARRIER FENCE	653.50	14			
									1210		1210		LF	PROJECT DEMARCATION FENCE	653.55	14			
								225			225		SF	TRAFFIC SIGNS, TYPE A	675.20	15			

PROJECT NAME: LUDLOW
PROJECT NUMBER: HES SGNL(44)
FILE NAME: t13b020_frm.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: M. BOGACZYK
QUANTITY SUMMARY SHEET 1
PLOT DATE: 4/19/2017
DRAWN BY: M. BOGACZYK
CHECKED BY: P. COBURN
SHEET 10 OF 43