STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																										
STA. 219+14.21, LT 40.44' (CONTINUED)	VERMONT 100	1	30	24	5.00																												M1-5 GREEN ON WHITE			E-136B
		1	21	15	2.19																												M6-3 GREEN ON WHITE			E-136B
STA. 221+07.62, RT 46.05'	← Okemo Ridge Rd Buttermilk Falls Rd →	1	36	36	9.00						2	Signs and posts installed 5/22/18. 12.75' post assembly (2.5' anchor), 14.25' post assembly (4' anchor).					X		X														W2-7L BLACK ON YELLOW			
		1	60	15	6.25																												W16-8aP BLACK ON YELLOW		44	
STA. 223+57.48, RT 0.80'		1	24	30	5.00						1	Signs and post installed 5/22/18. 14.25' post assembly (3' anchor).					X		X															R4-7		
		1	18	18	2.25																												OM1-1			
STA. 224+45.41, LT 32.27'	↑ Okemo Mtn SKI AREA 2	1	72	12	6.00						2	Signs and posts installed 5/17/18. 14' post assembly (4' anchor), 15' post assembly (4' anchor).					X		X															VD1-1A			T-93
	↑ Ludlow 2	1	72	12	6.00																												VD1-1A			T-93
	← Tyson 4	1	72	12	6.00																												VD1-1A			T-93
	← Plymouth 9	1	72	12	6.00																												VD1-1A			T-93
STA. 226+05.41, LT 31.50'		1	36	36	9.00						2	Signs and posts installed 5/17/18. 13.75' post assembly (4' anchor), 14.75' post assembly (4' anchor).					X		X															Moved to STA 227+07 LT to better make the directional signs at STA 224+45.41 LT visible.	W3-3		
STA. 275+72.16, LT		1	36	36	9.00				1		2	Signs and posts installed 5/17/18. 13.75' post assembly (4' anchor).					X		X															Moved to (VT-100) STA 277+15 LT to replace "Stop Ahead" sign.	W3-3		
(VT-100) STA 268+42.48 RT	MM 0408								1																								Salvaged to bridge plaque post at (VT-100) STA 268+45 LT.			
SHEET TOTALS					SF 209.78	SF	EA	SF				FT	FT	FT	FT	FT 135	FT 465		EA	LB	LB	LB	EA	LB	LB	LB	LB	EA	EA	LB						

SHSM = 2004 FHWA STANDARD HIGHWAY SIGNS & MARKINGS/2012 SUPP.
FYG = FLUORESCENT YELLOW GREEN

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: LUDLOW
PROJECT NUMBER: HES SGNL(44)

FILE NAME: t13b020_frm.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: M. BOGACZYK
TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 4/19/2017
DRAWN BY: M. BOGACZYK
CHECKED BY: P. COBURN
SHEET 33 OF 43