

QUANTITY SHEET 1

| SUMMARY OF ESTIMATED QUANTITIES | | | | | | | | | | TOTALS | | DESCRIPTIONS | | | | DETAILED SUMMARY OF QUANTITIES | | | |
|---------------------------------|--|--|--|--|--|--|--|---------|-----------------|-----------------|-------------|--------------|------|---|-------------|--------------------------------|---|---|-------|
| | | | | | | | | ROADWAY | EROSION CONTROL | FULL C.E. ITEMS | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | ROUND | QUANTITIES | UNIT | ITEMS |
| | | | | | | | | 5557 | | | 5557 | | CY | COMMON EXCAVATION | 203.15 | 55 | 203.15 - COMMON EXCAVATION | | |
| | | | | | | | | 556 | | | 556 | | CY | SOLID ROCK EXCAVATION | 203.16 | EST. | 5502 CY | US ROUTE 2 | |
| | | | | | | | | 2897 | | | 2897 | | SY | COLD PLANING, BITUMINOUS PAVEMENT | 210.10 | 29 | 55 CY | ROUNDING | |
| | | | | | | | | 5568 | | | 5568 | | CY | SUBBASE OF DENSE GRADED CRUSHED STONE | 301.35 | 55 | 5557 CY | TOTAL - COMMON EXCAVATION | |
| | | | | | | | | 348 | | | 348 | | CWT | EMULSIFIED ASPHALT | 404.65 | 3 | 203.16 - SOLID ROCK EXCAVATION | | |
| | | | | | | | | 1 | | | 1 | | LU | PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.) | 406.50 | -- | 556 CY | US ROUTE 2 | |
| | | | | | | | | 3820 | | | 3820 | | TON | SUPERPAVE BITUMINOUS CONCRETE PAVEMENT | 490.30 | 38 | EST. CY | ROUNDING | |
| | | | | | | | | 1 | | | 1 | | LU | AIR VOIDS PAY ADJUSTMENT (N.A.B.I.) | 490.31 | -- | 556 CY | TOTAL - SOLID ROCK EXCAVATION | |
| | | | | | | | | 1 | | | 1 | | LU | MAT DENSITY PAY ADJUSTMENT (N.A.B.I.) | 490.32 | -- | 301.35 - SUBBASE OF DENSE GRADED CRUSHED STONE | | |
| | | | | | | | | 1 | | | 1 | | LU | SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.) | 490.33 | -- | 5513 CY | US ROUTE 2 | |
| | | | | | | | | 2 | | | 2 | | TON | DUST AND ICE CONTROL WITH CALCIUM CHLORIDE | 609.15 | 0.1 | 55 CY | ROUNDING | |
| | | | | | | | | 20 | | | 20 | | EACH | STEEL MARKER POSTS | 619.16 | 4 | 5568 CY | TOTAL - SUBBASE OF DENSE GRADED CRUSHED STONE | |
| | | | | | | | | 1860 | | | 1860 | | LF | TEMPORARY TRAFFIC BARRIER | 621.90 | 36 | 490.30 SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY) | | |
| | | | | | | | | 1860 | | | 1860 | | LF | REMOVE AND RESET TEMPORARY TRAFFIC BARRIER | 621.95 | 36 | 3473 TON | US ROUTE 2 | |
| | | | | | | | | 80 | | | 80 | | HR | UNIFORMED TRAFFIC OFFICERS | 630.10 | EST. | 88 TON | EB RAMP | |
| | | | | | | | | 480 | | | 480 | | HR | FLAGGERS | 630.15 | EST. | 87 TON | WB RAMP | |
| | | | | | | | | | | 1 | 1 | | LS | FIELD OFFICE, ENGINEERS | 631.10 | -- | 134 TON | CLAY POINT ROAD | |
| | | | | | | | | | | 1 | 1 | | LS | TESTING EQUIPMENT, BITUMINOUS | 631.17 | -- | 38 TON | ROUNDING | |
| | | | | | | | | | | 3000 | 3000 | | DL | FIELD OFFICE TELEPHONE (N.A.B.I.) | 631.26 | -- | 3820 TON | TOTAL - SUPERPAVE BIT. CONCRETE PAVEMENT | |
| | | | | | | | | 1 | | | 1 | | LS | MOBILIZATION/DEMobilIZATION | 635.11 | -- | 900.675 SPECIAL PROVISION (HAND PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES) | | |
| | | | | | | | | 1 | | | 1 | | LS | TRAFFIC CONTROL (COLCHESTER HES 028-1(28)) | 641.10 | -- | 48 SY | CLAY POINT ROAD DRIVES | |
| | | | | | | | | 2 | | | 2 | | EACH | PORTABLE CHANGEABLE MESSAGE SIGN | 641.15 | -- | 2 SY | ROUNDING | |
| | | | | | | | | 6811 | | | 6811 | | LF | DURABLE 4 INCH WHITE LINE, POLYUREA | 646.404 | 67 | 50 SY | TOTAL - HAND PLACED BIT. CONC. PAVEMENT, DRIVES | |
| | | | | | | | | 6860 | | | 6860 | | LF | DURABLE 4 INCH YELLOW LINE, POLYUREA | 646.414 | 68 | | | |
| | | | | | | | | 164 | | | 164 | | LF | DURABLE 8 INCH WHITE LINE, POLYUREA | 646.444 | 2 | | | |
| | | | | | | | | 522 | | | 522 | | LF | DURABLE 8 INCH YELLOW LINE, POLYUREA | 646.454 | 5 | | | |
| | | | | | | | | 80 | | | 80 | | LF | DURABLE 24 INCH STOP BAR, POLYUREA | 646.484 | 1 | | | |
| | | | | | | | | 48 | | | 48 | | EACH | DURABLE LETTER OR SYMBOL, POLYUREA | 646.494 | -- | | | |
| | | | | | | | | 11350 | | | 11350 | | LF | TEMPORARY 4 INCH WHITE LINE, PAINT | 646.602 | 112 | | | |
| | | | | | | | | 11390 | | | 11390 | | LF | TEMPORARY 4 INCH YELLOW LINE, PAINT | 646.612 | 113 | | | |
| | | | | | | | | 60 | | | 60 | | LF | TEMPORARY 24 INCH STOP BAR, PAINT | 646.682 | 8 | | | |
| | | | | | | | | 8 | | | 8 | | EACH | TEMPORARY LETTER OR SYMBOL, PAINT | 646.692 | -- | | | |
| | | | | | | | | | 100 | | 100 | | LB | SEED | 651.15 | 1 | | | |
| | | | | | | | | | 830 | | 830 | | LB | FERTILIZER | 651.18 | 8 | | | |
| | | | | | | | | | 3.3 | | 3.3 | | TON | AGRICULTURAL LIMESTONE | 651.20 | 0.1 | | | |
| | | | | | | | | | 3.3 | | 3.3 | | TON | HAY MULCH | 651.25 | 0.1 | | | |
| | | | | | | | | | 890 | | 890 | | CY | TOPSOIL | 651.35 | 9 | | | |
| | | | | | | | | | 1 | | 1 | | LS | EPSC PLAN | 652.10 | -- | | | |
| | | | | | | | | | 80 | | 80 | | HR | MONITORING EPSC PLAN | 652.20 | EST. | | | |
| | | | | | | | | | 1 | | 1 | | LU | MAINTENANCE OF EPSC PLAN (N.A.B.I.) | 652.30 | -- | | | |

PROJECT NAME: COLCHESTER
PROJECT NUMBER: HES 028-1(28)
FILE NAME: t13b028frm.dgn PLOT DATE: 12/15/2015
PROJECT LEADER: P. COBURN DRAWN BY: M. BOGACZYK
DESIGNED BY: M. BOGACZYK CHECKED BY: M. LACROIX
QUANTITY SHEET 1 SHEET 24 OF 91