


ACCEPTED

## Heavy Duty Pole Package with Anchor Bolts



### Specifications

#### Domed Pole Cap 203-00010

Cast Aluminum, zinc plated, fits 4½" outer diameter pole  
(3X) ¼" x ½" square head machine screws

#### Mounting Brackets 101802

(2X) Z-bracket single sided round pole mounting bracket,  
Aluminum.  
(2X) ⅝" x ⅝" bolt and nut set  
(2X) ⅝" x 1¾" bolt and nut set

#### Round Aluminum Pole

(10' 373-10, 13' 373-13, 15' 373-15)

Schedule 40 aluminum pole, 4 ¼" outer diameter,  
one end threaded

#### Pedestal Base (203-00014)

Cast aluminum, threaded collar, Aluminum access door, FHWA  
certified, meets or exceeds AASHTO break-away requirements

#### Bent Anchor Bolt (111644, 3177-42)

(4X) ¾" x 18", galvanized steel bent anchor (foundation bolt),  
nut and washer (for frost free areas)  
or  
(4X) 1" x 42", galvanized steel bent anchor (foundation bolt), nut  
and washer (for frost or snow-cover areas)



1-800-236-0112 www.tapconet.com



Contract Holder  
GS-07F-5924R  
GS-07F-0234U