

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
					ROADWAY	BRIDGE NO. SE	BRIDGE NO. SW	BRIDGE NO. 13E	BRIDGE NO. 15E	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					1						1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
							20				20		CY	STRUCTURE EXCAVATION	204.25				
							20				20		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
						302	302	254	271		1129		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
						12	13	17	9		51		CWT	EMULSIFIED ASPHALT	404.65				
					1						1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
						30	37	38	22		127		GAL	WATER REPELLENT, SILANE	514.10				
						38	38	62	82		220		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
						780	830	1367	408		3385		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
						74	74	60	76		284		LF	JOINT SEALER, HOT POURED	524.11				
						968	1017	1514	644		4143		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
							30				30		CY	CONTROLLED DENSITY (FLOWABLE) FILL	541.45				
						39	42	69	21		171		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
						117	125	205	62		509		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
						3	3	31	3		40		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
						10	30	20	10		70		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS II	580.14				
						7018	7462	12300	3667		30447		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
						10	10	10	10		40		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
						5	5		5		15		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
						5	5		5		15		HR	TRUCK RENTAL	608.37				
						221	235	388	116		960		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
							20				20		CY	STONE FILL, TYPE II	613.11				
						16	17	33	8		74		GAL	REPOINTING GRANITE BRIDGE CURB	616.225				
						3	2	2	2		9		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
						661	673	226	581		2141		LF	TEMPORARY TRAFFIC BARRIER	621.90				
						661	673	226	581		2141		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
						74	79	130	39		322		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						150	150	150	150		600		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
					1						1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
								1			1		LS	TRAFFIC CONTROL (US ROUTE 4 - BRIDGE NO. 13E)	641.10				
									1		1		LS	TRAFFIC CONTROL (US ROUTE 4 - BRIDGE NO. 15E)	641.10				
						1					1		LS	TRAFFIC CONTROL (US ROUTE 4 - BRIDGE NO. 5E)	641.10				
							1				1		LS	TRAFFIC CONTROL (US ROUTE 4 - BRIDGE NO. 5W)	641.10				
						2	2	2	2		8		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						1	1	1	1		4		EACH	PORTABLE ARROW BOARD	641.16				
						400	450	700	350		1900		LF	6 INCH WHITE LINE	646.214				

PROJECT NAME: FAIR HAVEN-WEST RUTLAND  
PROJECT NUMBER: BF MEMB(35)

FILE NAME: z13b062-qss.dgn  
PROJECT LEADER: JPB  
DESIGNED BY: SRB  
QUANTITY SHEET 1

PLOT DATE: 1/20/2015  
DRAWN BY: SRB  
CHECKED BY: AEG  
SHEET 3 OF 44