

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
			ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEM	BRIDGE (ALTERNATE A)	BRIDGE (ALTERNATE B)	BRIDGE (ALTERNATE C)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													BEGIN OPTION DD					
					1					1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB NO. 2)	540.10				
					1					1		LS	SPECIAL PROVISION (CONTRACTOR FABRICATED PRECAST CONCRETE STRUCTURE)(APPROACH SLAB NO. 2)	900.645				
													END OPTION DD					
													BEGIN OPTION EE					
			58							58		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215				
			58							58		LF	18" PCCSP .079 (2-2/3 X 1/2)	601.0416				
			58							58		LF	18" RCP CLASS III	601.0815				
			58							58		LF	18" CPEP	601.0915				
			58							58		LF	18" CPPP (SL)	601.2815				
													END OPTION EE					
				1						1		MGAL	DUST CONTROL WITH WATER	609.10				
				570						570		CY	STONE FILL, TYPE IV	613.13				
			1							1		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10				
			209							209		LF	BOX BEAM GUARDRAIL	621.30				
			4							4		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51				
			4							4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 3 RAIL BOX BEAM	621.725				
			302							302		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
			240							240		HR	FLAGGERS	630.15				
						1				1		LS	FIELD OFFICE, ENGINEERS	631.10				
						1				1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
						1				1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
						3000				3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
			1							1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
			1							1		LS	TRAFFIC CONTROL	641.10				
			5							5		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
			890							890		LF	4 INCH WHITE LINE	646.20				
			900							900		LF	4 INCH YELLOW LINE	646.21				
				350						350		SY	GEOTEXTILE UNDER STONE FILL	649.31				
				480						480		SY	GEOTEXTILE FOR SILT FENCE	649.51				
				130						130		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
				25						25		LB	SEED	651.15				
				175						175		LB	FERTILIZER	651.18				
				1						1		TON	AGRICULTURAL LIMESTONE	651.20				
				1						1		TON	HAY MULCH	651.25				
				140						140		CY	TOPSOIL	651.35				
				250						250		SY	GRUBBING MATERIAL	651.40				
				1						1		LS	EPSC PLAN	652.10				
				20						20		HR	MONITORING EPSC PLAN	652.20				
				1						1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				

PROJECT NAME:	WESTON
PROJECT NUMBER:	BF 013-2(13)
FILE NAME:	z13b076qs.dgn
PROJECT LEADER:	S.E. BURBANK
DESIGNED BY:	M.C. SCOTT
QUANTITY SHEET #2	
PLOT DATE:	10/19/2015
DRAWN BY:	M.C. SCOTT
CHECKED BY:	J.J. WESTCOTT
SHEET	10 OF 82

