



THIS REFLECTORIZED ALUMINUM DELINEATION DEVICE IS TO BE ERRECTED EVERY 36 FEET, AT SPLICES. DELINEATOR SHALL MEET SPECIFICATION REQUIRMENTS FOR ASTM B209 ALLOY 5052-H32.

REFLECTIVE MATERIAL SHALL MEET THE REQUIREMENTS OF SUBSECTION 750.09 AND SHALL BE OF ENCAPSULATED LENS SILVER OR AMBER. AMBER IS TO BE INSTALLED ON THE LEFT OR MEDIAN SIDE OF INTERSTATE ROADWAYS OR RAMP.

BOX BEAM GUARD RAIL DETAILS
NOT TO SCALE



PROJECT NAME: WESTON	PLOT DATE: 10/2/2015
PROJECT NUMBER: BF 013-2(13)	DRAWN BY: K.C. BARRY
FILE NAME: z13b076bratl.dgn	CHECKED BY: S.E. BURBANK
PROJECT LEADER: S.E. BURBANK	SHEET 54 OF 68
DESIGNED BY: K.C. BARRY	
BOX BEAM GUARD RAIL DETAILS	