

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES								TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
				ROADWAY	EROSION CONTROL	BRIDGE NO. 2	BRIDGE NO. 13E	FULL C.E. ITEMS	BRIDGE NO. 13W	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						55				55		CY	COMMON EXCAVATION	203.15				
						55				55		CY	EARTH BORROW	203.30				
						1	1		1	3		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
						1				1		LS	STRUCTURAL STEEL (BRIDGE NO. 2 OVER US ROUTE 4)	506.75				
							1			1		LS	STRUCTURAL STEEL (US ROUTE 4 - BRIDGE NO. 13E)	506.75				
									1	1		LS	STRUCTURAL STEEL (US ROUTE 4 - BRIDGE NO. 13W)	506.75				
						120	120		120	360		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
						1170	1170		1170	3510		LF	TEMPORARY TRAFFIC BARRIER	621.90				
						300	300		300	900		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						300	300		300	900		HR	FLAGGERS	630.15				
								1		1		LS	FIELD OFFICE, ENGINEERS	631.10				
								1		1		LS	TESTING EQUIPMENT, PROTECTIVE COATINGS	631.18				
								3000		3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
								540		540		HR	EMPLOYEE TRAINEESHIP	634.10				
				1						1		LS	MOBILIZATION/DEMOLITION	635.11				
						1				1		LS	TRAFFIC CONTROL (BRIDGE NO. 2 OVER US ROUTE 4)	641.10				
							1			1		LS	TRAFFIC CONTROL (US ROUTE 4 - BRIDGE NO. 13E)	641.10				
									1	1		LS	TRAFFIC CONTROL (US ROUTE 4 - BRIDGE NO. 13W)	641.10				
						30	30		30	90		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17				
						1545	1545		1545	4635		LF	6 INCH WHITE LINE	646.214				
						3090	3090		3090	9270		LF	TEMPORARY 6 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6211				
						3090	3090		3090	9270		LF	TEMPORARY 6 IN YELLOW LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6311				
						550				550		LF	TEMPORARY 12 IN WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6611				
						170	170		170	510		SF	PAVEMENT MARKING MASK	646.86				
					1100					1100		SY	GEOTEXTILE FOR SILT FENCE	649.51				
						30				30		LB	SEED	651.15				
						10				10		LB	FERTILIZER	651.18				
						0.6				0.6		TON	AGRICULTURAL LIMESTONE	651.20				
						0.6				0.6		TON	HAY MULCH	651.25				
					2200					2200		SY	TEMPORARY EROSION MATTING	653.20				
						1				1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES) (BR.NO.2 OVER US 4)	900.645				
									1	1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES) (US 4-BR. NO. 13W)	900.645				
							1			1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES)(US 4-BR. NO. 13E)	900.645				
						1				1		LS	SPECIAL PROVISION (QC/QA CLEAN AND PAINT EXISTING STEEL STRUCTURES, BARE STEEL)(BR.NO.2 OVER US 4)	900.645				
							1			1		LS	SPECIAL PROVISION (QC/QA CLEAN AND PAINT EXISTING STEEL STRUCTURES, BARE STEEL)(US 4-BR NO. 13E)	900.645				
									1	1		LS	SPECIAL PROVISION (QC/QA CLEAN AND PAINT EXISTING STEEL STRUCTURES, BARE STEEL)(US 4-BR NO. 13W)	900.645				
						1				1		LS	SPECIAL PROVISION (REMOVAL OF EXISTING GREASE COATING) (BRIDGE NO. 2 OVER US ROUTE 4)	900.645				

## QUANTITY SHEET (1)

PROJECT NAME: CASTLETON-WEST RUTLAND  
PROJECT NUMBER: BF BPNT (I5)

FILE NAME: z525459qs.dgn  
PROJECT LEADER: G.K.DONINGTON  
DESIGNED BY: R.GAUDREAU  
qs.dgn

PLOT DATE: 17-OCT-2014  
DRAWN BY: R.GAUDREAU  
CHECKED BY: S.BROWN  
SHEET 5 OF 14

