

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	EROSION CONTROL	BRIDGE NO. 11	BRIDGE NO. D15	BRIDGE NO. 16N	BRIDGE NO. 56C	FULL C.E. ITEMS	BRIDGE NO. 16S		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				27	93			93		213		CY	COMMON EXCAVATION	203.15				
				27	93			93		213		CY	EARTH BORROW	203.30				
			1	1	1	1		1		5		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
				1						1		LS	STRUCTURAL STEEL (TH 14 OVER US 7 - BRIDGE NO. D15)	506.75				
			1							1		LS	STRUCTURAL STEEL (US 7 - BRIDGE NO. 11)	506.75				
												LS	STRUCTURAL STEEL (US 7 - BRIDGE NO. 16N)	506.75				
												LS	STRUCTURAL STEEL (US 7 - BRIDGE NO. 56C)	506.75				
												LS	STRUCTURAL STEEL (US 7 - BRIDGE NO.16S)	506.75				
			120	120	120	120		120		600		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
			40							40		LF	REMOVING AND RESETTING FENCE	620.50				
			520	1060	2704	655		2704		7643		LF	TEMPORARY TRAFFIC BARRIER	621.90				
			300	300	300	300		300		1500		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
			300	300	300	300		300		1500		HR	FLAGGERS	630.15				
												LS	FIELD OFFICE, ENGINEERS	631.10				
												LS	TESTING EQUIPMENT, PROTECTIVE COATINGS	631.18				
												DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
												HR	EMPLOYEE TRAINEESHIP	634.10				
												LS	MOBILIZATION/DEMobilIZATION	635.11				
				1						1		LS	TRAFFIC CONTROL (TH 14 OVER US 7 - BRIDGE NO. D15)	641.10				
			1							1		LS	TRAFFIC CONTROL (US 7 - BRIDGE NO. 11)	641.10				
					1					1		LS	TRAFFIC CONTROL (US 7 - BRIDGE NO. 16N)	641.10				
						1				1		LS	TRAFFIC CONTROL (US 7 - BRIDGE NO. 56C)	641.10				
												LS	TRAFFIC CONTROL (US 7 - BRIDGE NO.16S)	641.10				
			30	30	30	30		30		150		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17				
			725	1420	3079	655		3079		8958		LF	6 INCH WHITE LINE	646.214				
			1450	2840	6158	1310		6158		17916		LF	TEMPORARY 6 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6211				
			1450	2840	6158	1310		6158		17916		LF	TEMPORARY 6 IN YELLOW LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6311				
					400			400		800		LF	TEMPORARY 12 IN WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6611				
					16			16		32		LF	TEMPORARY 24 INCH STOP BAR, TEMPORARY PAVEMENT MARKING TAPE	646.6811				
			200	200	1200	200		1200		3000		SF	PAVEMENT MARKING MASK	646.86				
			1100							1100		SY	GEOTEXTILE FOR SILT FENCE	649.51				
				10	30			30		70		LB	SEED	651.15				
				10	10			10		30		LB	FERTILIZER	651.18				
				0.6	0.6			0.6		1.8		TON	AGRICULTURAL LIMESTONE	651.20				
				0.2	0.6			0.6		1.4		TON	HAY MULCH	651.25				
			2200							2200		SY	TEMPORARY EROSION MATTING	653.20				
				1						1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES) (TH 14-BR. NO. D15)	900.645				
			1							1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES) (US 7 - BR. NO. 11)	900.645				
										1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES) (US 7 - BR. NO. 16S)	900.645				

(RE-ADVERTISED)



PROJECT NAME: BENNINGTON - MT TABOR

PROJECT NUMBER: BF BPNT (16)

FILE NAME: z5254510qs.dgn

PROJECT LEADER: G.K.DONINGTON

DESIGNED BY: S.BROWN

qs_l.dgn

PLOT DATE: 16-MARCH-2015

DRAWN BY: S.BROWN

CHECKED BY: A.STOCKIN

SHEET 5 OF 23