

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES						TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES						
					ROADWAY	BRIDGE	FULL CE ITEMS	ROADWAY (ALTERNATE A)	ROADWAY (ALTERNATE B)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					22650					22650		LF	SHOULDER BERM REMOVAL	203.40	257			
					1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.			
					37000					37000		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	277			
					23080					23080		LF	MILLED RUMBLE STRIPS	213.10	228			
					2250					2250		TON	AGGREGATE SHOULDERS	402.12	11			
					1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	EST.			
					14150					14150		LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD	417.20	142			
					4240					4240		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	43			
					1					1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-			
					1					1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-			
						150				150		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	25			
						100				100		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.			
					15					15		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	EST.			
					2					2		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.			
					10					10		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	EST.			
					70					70		HR	POWER GRADER RENTAL	608.15	EST.			
					90					90		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
					180					180		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
					70					70		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			
					70					70		HR	TRUCK RENTAL	608.37	EST.			
					1000					1000		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
					2600					2600		HR	FLAGGERS	630.15	EST.			
							1			1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
							1			1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
							3000			3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
					1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
					1					1		LS	TRAFFIC CONTROL	641.10	-			
					5					5		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
					138000					138000		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	1427			
					135700					135700		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	1404			
													BEGIN OPTION AA					
					680					680		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	6			
					680					680		LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	6			
													END OPTION AA					
													BEGIN OPTION BB					
					194					194		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	4			
					194					194		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	4			
													END OPTION BB					

PROJECT NAME:	WAITSFIELD-MORETOWN
PROJECT NUMBER:	STP SURF(39)
FILE NAME: p13b168.dgn	PLOT DATE: 05/05/2014
PROJECT LEADER: M. FOWLER	DRAWN BY: L. BULLOCK
DESIGNED BY: L. BULLOCK	CHECKED BY: M. FOWLER
QUANTITY SHEET #1	SHEET 6 OF 26