

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
						ROADWAY	BRIDGE	FULL CE ITEMS	ROADWAY (ALTERNATE A)	ROADWAY (ALTERNATE B)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
														BEGIN OPTION CC						
						190					190		LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	15			ALTERNATE A (ZA1)	
						190					190		LF	DURABLE CROSSWALK MARKING, POLYUREA	646.504	15			SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	
														END OPTION CC						
						156000					156000		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	1338	255,516	SY	MAINLINE	
						154000					154000		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	1510	2,564	SY	ROUNDING	
						680					680		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	6	258,080	SY	TOTAL	
						194					194		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	4			ALTERNATE B (ZA2)	
						190					190		LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	15			SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)	
						5300					5300		EACH	LINE STRIPING TARGETS	646.76	303	14,905	TON	MAINLINE	
						144500					144500		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	384	155	TON	ROUNDING	
						1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-	15,060	TON	TOTAL	
						10000					10000		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	EST.				
						69410					69410		SY	SPECIAL PROVISION (HOT-IN-PLACE RECYCLE)	900.675	691				
						50					50		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.				
						330					330		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	4				
						64					64		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	0.7				
														BEGIN ALTERNATE ZA1						
									258080		258080		SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675					
														END ALTERNATE ZA1						
														BEGIN ALTERNATE ZA2						
										1	1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31					
										15060	15060		TON	SPECIAL PROVISION (6.3 MM POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)	900.680					
										1710	1710		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683					
														END ALTERNATE ZA2						