STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 37

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	~~SALV TIS SIGN~~ REM	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	REQUIRED SIGNS	REMARKS	SIGN DETAIL S.H.S.M.*	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
																				1.3	1.7	1.7		7.6	9.0	10.8	14.6									
OPTION ITEMS																																				
US ROUTE 4																																				
W 159+35.2 RT	HIDDEN DRIVES LEFT	1	30	30	6.25						1					~~X~~ 13.0		1															INSTALL NEW SIGN ON NEW POST VW-054L			T-80
W 160+25.0 LT	SPEED LIMIT 45		24	30	0				1																								RETAIN EXISTING SIGN ON EXISTING POST			
W 160+61.7 RT		1	30	30	6.25			1	1																								INSTALL NEW SIGN ON EXISTING POST	W1-10L		
	30 MPH	1	18	18	2.25			1																									INSTALL NEW SIGN (SUB-MOUNT WITH PREVIOUS SIGN)	W13-1P (30)		
W 164+65.7 RT	ONE LANE BRIDGE	1	30	30	6.25			1	1																								INSTALL NEW SIGN ON EXISTING POST	W5-3		
W 164+72.8 RT	LEGAL LOAD LIMIT 16,000 POUNDS		24	30	0																												RETAIN EXISTING SIGN MOUNTED ON COVERED BRIDGE			
W 164+77.2 RT	CLEARANCE 10'-0"		30	30	0																												RETAIN EXISTING SIGN MOUNTED ON COVERED BRIDGE			
W 164+72.0 LT	STOP	1	30	30	6.25			1	1																								INSTALL NEW SIGN ON EXISTING POST	R1-1		
W 164+81.2 LT	LEFT LANE MUST TURN LEFT	1	30	30	6.25			1	1																								INSTALL NEW SIGN ON EXISTING POST	R3-7L		
W 164+89.7 RT	STOP	1	30	30	6.25			1			1					~~X~~ 13.0		1															INSTALL NEW SIGN ON NEW POST	R1-1		
	0040 1424 0311		6	10	0		1	1																									SALVAGE EXISTING SIGN (SUB- MOUNT BACK-TO-BACK WITH PREVIOUS SIGN)			
W 166+30.7 LT	ONLY	1	30	30	6.25			1	1																								INSTALL NEW SIGN ON EXISTING POST	R3-8		
W 166+39.5 RT		1	48	24	8.00			1	2																								INSTALL NEW SIGN ON EXISTING POSTS	W1-6L		
W 167+31.9 RT		1	48	24	8.00			1	2																								INSTALL NEW SIGN ON EXISTING POSTS	W1-6R		
												FT	FT	FT	FT	FT ~~30.0~~ 26.0	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 62.00	SF	EA. 1	EA. 10				FT			FT ~~30.0~~ 26.0					LB			EA.	LB				EA.	EA.	LB					

THE TOTAL LENGTH OF EACH POST HAS BEEN ASSUMED TO BE 15 FEET, WITH THE EXCEPTION OF POSTS FOR OBJECT MARKERS AND POSTS FOR BRIDGE PLAQUES AND MILE MARKERS WHICH HAVE BEEN ASSUMED TO BE 8 FEET AND 10 FEET PER POST, RESPECTIVELY. FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VAOT STANDARD SHEETS AND THE "SIGN POST DESIGN GUIDELINE".

*STANDARD HIGHWAY SIGNS AND MARKINGS BOOK

PROJECT NAME: KILLINGTON-WOODSTOCK
PROJECT NUMBER: ER NH 020-2(38)

FILE NAME: z13b192tss.dgn
PROJECT LEADER: E. ATKINS
DESIGNED BY: T. BIGELOW
TRAFFIC SIGN SUMMARY SHEET 37

PLOT DATE: 3/7/2016
DRAWN BY: I. KHALID
CHECKED BY: ATKINS/SOBEL
SHEET 112 OF 146