QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					BEGIN ITEMS COMMON TO ALL ALTERNATES		
	20,500		20,500	LF	SHOULDER BERM REMOVAL	203.40	EST
	1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
	3,750		3,750	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	107
	26,500		26,500	LF	MILLED RUMBLE STRIPS	213.10	EST
	1,000		1,000	TON	AGGREGATE SHOULDERS	402.12	100
	1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
	25,500		25,500	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD	417.20	EST
					(AASHTO M 324 (ASTM D 6690) TYPE II)		
	3,000		3,000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	75
	1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	50		50	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
	200		200	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
	200		200	HR	TRUCK RENTAL	608.37	EST
	375		375	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
	2,000		2,000	HR	FLAGGERS	630.15	EST
		1	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
		1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
		3,000	3,000	DL	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.26	-
	1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
	1		1	LS	TRAFFIC CONTROL	641.10	-
	3		3	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
	110,000		110,000	LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	EST
	105,000		105,000	LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	EST
	1,500		1,500	LF	DURABLE 8 INCH YELLOW LINE, POLYUREA	646.454	EST
					BEGIN OPTION AA		
	500		500	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	EST
	500		500	LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	EST
					END OPTION AA		
					BEGIN OPTION BB		
	122		122	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
	122		122	EA	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-
					END OPTION BB		
	110,000		110,000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST
	105,000		105,000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST
	1,500		1,500	LF	TEMPORARY 8 INCH YELLOW LINE, PAINT	646.652	EST
	500		500	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST
	122		122	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
	4,025		4,025	EA	LINE STRIPING TARGETS	646.76	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING, BITUMINOUS PAVEMENT
223	SY	BEGIN PROJECT
145	SY	END PROJECT
3,275	SY	TOWN HIGHWAYS, DRIVES & VT ROUTE 346
107	SY	ROUNDING
3,750	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (TYPE IVS)
100	TON	TOWN HIGHWAYS & VT ROUTE 346
2,825	TON	SPOT LEVELING
75	TON	ROUNDING
3,000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: POWNAL - BENNINGTON
PROJECT NUMBER: NH SURF (42)

FILE NAME: i3b592\pi3b592.dgn
PROJECT LEADER: FOWLER
DESIGNED BY: LOCKE
IPARM FILE NAME: pi3b592_05.i

PLOT DATE: 02-APR-2014
DRAWN BY: LOCKE
CHECKED BY: PAVT MGMT
SHEET 5 OF 23