QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	108,750		108,750	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST
	1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I)	690.50	-
	1,725		1,725	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	EST
	50		50	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST
	250		250	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	EST
	100		100	CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	25.75
					END ITEMS COMMON TO ALL ALTERNATES		
					BEGIN ALTERNATE A		
	216,500		216,500	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	1,380
					END ALTERNATE A		
					BEGIN ALTERNATE B		
	1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	12,750		12,750	TON	SPECIAL PROVISION (6.3 MM POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT) (SBR OR SBS POLYMER)	900.680	100
	1,550		1,550	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	104
					END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE A
		SPECIAL PROVISION (PAVER-PLACED SURFACE TREATMENT, TYPE C)
213,570	SY	MAINLINE
1,550	SY	TOWN HIGHWAYS & VT 346 APPROACHES
1,380	SY	ROUNDING
216,500	SY	TOTAL
		ALTERNATE B
		SPECIAL PROVISION (6.3 MM POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)
12,550	TON	MAINLINE
100	TON	TOWN HIGHWAYS & VT 346 APPROACHES
100	TON	ROUNDING
12,750	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: POWNAL - BENNINGTON
PROJECT NUMBER: NH SURF (42)

FILE NAME: 13b592\pl3b592.dgn
PROJECT LEADER: FOWLER
DESIGNED BY: LOCKE
IPARM FILE NAME: pl3b592_06.1

PLOT DATE: 02-APR-2014
DRAWN BY: LOCKE
CHECKED BY: PAVT MGMT
SHEET 6 OF 23