STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES								TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	BRIDGE	FULL E&C ITEMS	ROADWAY (ALTERNATE A)	ROADWAY (ALTERNATE B)				GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
164700								164700		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST			
1550								1550		LF	TEMPORARY 8 INCH WHITE LINE, PAINT	646.642	EST			
3650								3650		LF	TEMPORARY 8 INCH YELLOW LINE, PAINT	646.652	EST			
650								650		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST			
232								232		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
250								250		LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	EST			
6008								6008		EACH	LINE STRIPING TARGETS	646.76	EST			
1450								1450		LF	PAINTED CURB	646.81	EST			
188800								188800		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST			
1								1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
1								1		EACH	SPECIAL PROVISION (PEDESTRIAN SIGNAL HEADS, COUNTDOWN)(US ROUTE 7 @ CENTER PLAZA)	900.620	-			
1								1		EACH	SPECIAL PROVISION (PEDESTRIAN SIGNAL HEADS, COUNTDOWN)(US ROUTE7 @ MIDDLE RD.)	900.620	-			
1								1		EACH	SPECIAL PROVISION (VEHICLE STOP BAR DETECTION SYSTEM) (US ROUTE 7 @ CENTER PLAZA)	900.620	-			
1								1		EACH	SPECIAL PROVISION (VEHICLE STOP BAR DETECTION SYSTEM) (US ROUTE 7 @ MIDDLE RD.)	900.620	-			
4125								4125		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	EST			
150								150		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST			ALTERNATE (ZA1)
500								500		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	26			SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)
120								120		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	6	369318	SY	MAINLINE
											BEGIN ALTERNATE ZA1			1,682	SY	ROUNDING
			371000					371000		SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	1682	371,000	SY	TOTAL
											END ALTERNATE ZA1					
											BEGIN ALTERNATE ZA2					ALTERNATE (ZA2)
					1			1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-			SPECIAL PROVISION (6.3MM POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT) (SBR OR SBS POLYMER)
					21700			21700		TON	SPECIAL PROVISION (6.3 MM POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)	900.680	165	21,535	TON	MAINLINE
														165	TON	ROUNDING
					2600			2600		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	115	21,700	TON	TOTAL
											END ALTERNATE ZA2					

PROJECT NAME: BRANDON - MIDDLEBURY
PROJECT NUMBER: NH SURF(43)

FILE NAME: pl3B616_Brandon-Middlebury.dgn PLOT DATE: 20-JUN-2014
PROJECT LEADER: M. FOWLER DRAWN BY: N. PAPPAS
DESIGNED BY: N. PAPPAS CHECKED BY: M. FOWLER
QUANTITY SHEET 2 SHEET 7 OF 28