DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
STOWE VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.000		BEGINNING OF CLASS 1 SECTION OF ROADWAY (NORTHBOUND) NOTE: STICKERS ON BACK OF SIGNS IN CLASS 1 SECTION OF STOWE SHALL HAVE "STOWE, DATE (MM/YY), TH-2"																									
NB	0.016	A	M3-1	24	12	GRN/WHT	✳ NORTH / VERMONT 108 6/17	2.00								1		14.0 X									INSTALL AT SOUTHERN MOST EDGE OF GARDEN, ABUTTING ROCK WALL	X		
		A	M1-5	30	24	GRN/WHT	✳ 6/17	5.00																					E-136B
NB	0.032	A	R2-1	24	30		SPEED LIMIT 25 8/1						1		X														
		A	R2-1	24	30		✳ SPEED LIMIT 25 8/1	5.00								1		15.0 X										X		
NB	0.050	A	W11-2	30	30	FYG	PEDESTRIAN SYMBOL 6/17						1		X														
		A	W16-7P	21	15	FYG	DIAGONAL ARROW WARNING 6/17						1																
		A	W11-2	30	30	FYG	✳ TRIM 7/8 TRIM 6/17	6.25								1		16.5 X										X		
		A	W16-7PL	24	12	FYG	✳ 6/17	2.00																				X		
NB	0.124	A	W11-2	30	30	FYG	PEDESTRIAN SYMBOL TRIM 6/17						1		X														
		A	W16-7P	21	15	FYG	DIAGONAL ARROW WARNING 6/17						1																
		A	W11-2	30	30	FYG	6/17	6.25								1		15.25 X										X		
		A	W16-7PL	24	12	FYG	6/17	2.00																				X		
NB	0.157	A	R2-1	24	30		SPEED LIMIT 25 6/17						1		X														
		A	R2-1	24	30		SPEED LIMIT 25 6/17	5.00								1		14.0 X										X		
SIGN SUMMARY SHEET							SHEET TOTALS	33.50 SF	0.00 SF	0 EA	0 EA	0 EA	6 EA	0 EA	0 EA	5 EA		74.75 ~~75.0~~ FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	418.6	0.0	36	15	6	85	0	0	79		1185.0		0	0.0								

PROJECT NAME: STOWE - BERKSHIRE
PROJECT NUMBER: STPG SIGN (49)
FILE NAME: 01 STOWE VT-108 NB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: J. BLANCHARD
STOWE NB SHEET 1
PLOT DATE: 6/24/2015
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 15 OF 131

✳ THESE 5 SIGNS MOVED 50' AHEAD AT REQUEST OF TOWN OF STOWE