DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
STOWE VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.149	A	W1-4R	30	30		RIGHT REVERSE CURVE 6/20						1		X														
NB	2.173	A	R2-1	24	30		SPEED LIMIT 40 6/20						1		X														
NB	2.188	A	R2-1	24	30		6/20	5.00								1		14.00 X									INSTALL 80 FT NORTH OF EXISTING, IN LINE WITH SB SPEED LIMIT 35 MPH SIGN	X		
NB	2.276	A	W1-4R	30	30		6/20	6.25								1		13.50 X									INSTALL 543 FT NORTH OF EXISTING SPEED LIMIT SIGN AT M.P. 2.173	X		
NB	2.587	A	VD-062M	72	16		BUSINESS SIGN 6/22			1				X														
		A	VD-062M	72	16		BUSINESS SIGN 6/22			1																		
		A	VD-062BM	72	16		BUSINESS SIGN 6/22			1																		
NB	2.779	A	R2-1	24	30		SPEED LIMIT 40 6/22						1		X														
		A	R2-1	24	30		TRIM 7/7 6/22	5.00								1		13.50 X									REQUIRES VEGETATION CLEARING	X		
NB	2.822	A/B	D3-1	UNK.	UNK.		LANDMARK LN PVT 6/22						1		X														
		A/B	D3-1	68	12		6/22	5.67								2		23.25 X									LANDMARK LN (PVT); FIELD LOCATE FOR VISIBILITY FROM VT 108		11	
NB	2.897	A/B	D3-1	UNK.	UNK.		HOUSTON FARM RD PVT 6/22						1		X														
		A/B	D3-1	68	12		6/22	5.67								2		22.75 X									HOUSTON FARM RD (PVT); FIELD LOCATE FOR VISIBILITY FROM VT 108		11	
NB	2.958	A	VW-054R	30	30		HIDDEN DRIVES RIGHT 6/22			1				X														
NB	3.116	A	VD-062B	72	16		BUSINESS SIGN 6/22			1				X														
SIGN SUMMARY SHEET							SHEET TOTALS	~~27.59~~ 27.58 SF	0.00 SF	5 EA	0 EA	0 EA	5 EA	0 EA	0 EA	7 EA		~~87.00~~ 105.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	418.6 SF	0.0 SF	36 EA	15 EA	6 EA	85 EA	0 EA	0 EA	79 EA		1185.0 FT		0 EA	0.0 LB							

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **01 STOWE VT-108 NB TSS.xls** PLOT DATE: **6/24/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
STOWE NB SHEET 8 SHEET **22** OF **131**