DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
STOWE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	7.523	F	R2-1	24	30		SPEED LIMIT 50 7/7			1				X															
SB	6.876	F	UNK.	UNK.	UNK.		BUSINESS SIGN 7/7			1				X															
SB	6.640	F	VW-205	30	30		WATCH FOR TURNING VEHICLES 6/10						1		X														
		F	VW-205	36	36		TRIM 7/7 6/10	9.00								2		25.00 X									10	
SB	5.943	F	W11-2	30	30	FYG	PEDESTRIAN SYMBOL 6/10						1		X														
		F	W16-9P	24	12	FYG	AHEAD WARNING 6/10						1																
		F	W11-2	30	30	FYG	6/10	6.25								1		15.50 X									X	
		F	W16-9P	24	12	FYG	6/10	2.00																			X		
SB	5.911	F	VW-205	30	30		WATCH FOR TURNING VEHICLES 6/10						1		X														
		F	VW-205	36	36		6/10	9.00								2		28.00 X									10	
SB	5.859	F	W11-2	30	30	FYG	PEDESTRIAN SYMBOL 6/10						1		X														
		F	W16-7P	24	12	FYG	DOWNWARD DIAGONAL ARROW 6/10						1																
SB	5.833	F	W11-2	30	30	FYG	6/10	6.25								1		29.25 X									INSTALL 137 FT SOUTH OF EXISTING	X		
		F	W16-7PL	24	12	FYG	6/10	2.00																			X		
SB	5.403	F	W7-1a	30	30		HILL WITH GRADE 6/10						1		X														
							SHEET TOTALS	34.50 SF	0.00 SF	2 EA	0 EA	0 EA	7 EA	0 EA	0 EA	6 EA		97.75 ~~90.0~~ FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
							TOWN DIRECTIONAL TOTALS	515.2	0.0	18	11	9	110	0	0	85		1275.0		0	0.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **02 STOWE VT-108 SB TSS.xls** PLOT DATE: **6/24/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
STOWE SB SHEET 2 SHEET **30** OF **131**