DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
STOWE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W7-1a	30	30		6/13	6.25								1		14.00 X								INSTALL 1070 FT NORTH OF SPEED REDUCTION WARNING	X		
SB	5.200	F	VR2-5A	24	30		REDUCED SPEED AHEAD 6/13						1		X														
		F	W3-5	36	36		6/13	9.00								2		27.25 X									X		
SB	5.155	F	VD-062B	72	16		BUSINESS SIGN			1				X															
SB	5.112	F	R2-1	24	30		SPEED LIMIT 40 6/13						1		X														
		F	R2-1	30	36		TRIM 7/8 6/13	7.50								1		14.25 X									X		
SB	5.072	E/F	D3-1	UNK.	UNK.		RANCH BROOK RD						1		X														
		E/F	UNK.	UNK.	UNK.		ADAMS CAMP TRAILS				1		~~1~~ 0													SALVAGE AND REMOUNT IN NEW LOCATION			
SB	5.071	G	VR-017	24	30		LLL 16,000 LBS 6/10						~~1~~ 0		X														
		G	VR-017	24	30		6/10	5.00								1		11.75 X								RANCH BROOK RD (TH-34)		9	
SB	5.060	H	R1-1	30	30		STOP 6/10						1		X														
		G	VD-700	6	10		MILE MARKER 6/10				1	1	1													SALVAGE AND MOUNT ON NEW POST BELOW STOP SIGN			
		E/F	D3-1	64	12		6/10	5.33								2		23.25 X								RANCH BROOK RD (TH-34); FIELD LOCATE FOR VISIBILITY FROM VT-108		11	
		E/F	UNK.	UNK.	UNK.		ADAMS CAMP TRAILS 6/10					1														SALVAGE FROM OLD LOCATION; MOUNT BELOW STREET NAME SIGN			
SB	5.059	H	R1-1	30	30		6/10	6.25								1		14.00 X								RANCH BROOK RD (TH-34); INSTALL 10 FT NORTH OF EXISTING, IN LINE WITH END OF WOODEN RAIL	X		
SIGN SUMMARY SHEET							SHEET TOTALS	39.33	0.00	1	2	2	~~7~~ 5	0	0	8		~~120.0~~ 104.50		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	515.2	0.0	18	11	9	110	0	0	85		1275.0		0	0.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **02 STOWE VT-108 SB TSS.xls** PLOT DATE: **6/24/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
STOWE SB SHEET 3 SHEET **31** OF **131**