DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
STOWE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	2.370	F	W1-8	18	24		CHEVRON 6/14						1		X														
SB	2.388- 2.320	E/F	N/A	6	8		INSTALL (8) NEW DELINEATOR ASSEMBLIES 6/14																			INSTALL 8 BACK TO BACK DELINEATOR ASSEMBLIES AT 60 FT SPACINGS. SEE SHEET 4			
SB	2.292	E/F	D3-1	UNK.	UNK.		BUTTERNUT LN (PVT)						1		X														
		E/F	D3-1	68	12		6/14	5.67								2		22.00 X								BUTTERNUT LN (PVT)		11	
SB	2.277	F	VR2-5A	24	30		REDUCED SPEED AHEAD						1		X														
		F	W3-5	36	36		6/14	9.00								2		29.25 X									X		
SB	2.218	E/F	D3-1	UNK.	UNK.		STROM FARM LN (PVT)						1		X														
		E/F	D3-1	66	12		6/14	5.50								2		24.75 X								STROM FARM LN (PVT)		11	
SB	2.188	F	R2-1	24	30		SPEED LIMIT 30						1		X														
		F	R2-1	30	36		6/14	7.50								1		14.75 X									X		
SB	2.174	F	W11-2	30	30		PEDESTRIAN SYMBOL						1		X														
		F	W16-4P	24	18		NEXT 4500 FT						1																
		F	W11-2	30	30	FYG		6.25								1		17.50 X									X		
		F	W16-4P	30	24	FYG	6/14	5.00																			X		
SB	2.125	F	VD-062AS	72	16		BUSINESS SIGN			1				X															
SIGN SUMMARY SHEET							SHEET TOTALS	38.92	0.00	1	0	0	7	0	0	8		108.25 ~~120.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	515.2	0.0	18	11	9	110	0	0	85		1275.0		0		0.0							

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **02 STOWE VT-108 SB TSS.xls** PLOT DATE: **6/24/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
STOWE SB SHEET 7 SHEET **35** OF **131**