DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
STOWE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	VD-062B	72	16		BUSINESS SIGN 6/14			1																			
		F	VD-062B	72	16		BUSINESS SIGN 6/14			1																			
SB	2.101	F	VD-271	72	48		LANE ASSIGNMENT SIGN ALTERNATE ROUTE TO I89 NEXT RIGHT 6/14						1	X				31.00											
		F	VD-271	72	48		TRIM 7/7 (2) 6/14	24.00																			10	
SB	2.061	F	VW1-2M	30	30		MODIFIED LEFT TURN 6/14						1		X													
		F	VW-205	30	30		WATCH FOR TURNING VEHICLES 6/14						1															
		F	W1-10cL	36	36		NEED THIS NB ALSO STOWE PROVIDE SIGN 6/14	9.00								2	30.00 X							X		
		F	W16-8P	28	8		6/14	1.56																			6	
SB	2.036	F	M4-5	24	12		TO INTERSTATE 6/14						1		X													
		F	M1-1	24	24		INTERSTATE 89 6/14						1															
		F	M6-1	21	15		RIGHT ---> INTERSTATE 6/14						1															
		F	M4-5	24	12	WHT/ BLU	6/14	2.00								1	16.25 X										X		
		F	M1-1	24	24	WHT/ BLU	6/14	4.00																			X		
		F	M6-1	21	15	WHT/ BLU	6/14	2.19																			X		
SB	2.026	F	VD-062B	72	16		BUSINESS SIGN 6/14			1				X															
							SHEET TOTALS	42.74	0.00	3	0	0	6	0	0	3	~~45.0~~ 77.25			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	515.2	0.0	18	11	9	110	0	0	85	1275.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STOWE - BERKSHIRE
PROJECT NUMBER: STPG SIGN (49)

FILE NAME: 02 STOWE VT-108 SB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: J. BLANCHARD
STOWE SB SHEET 8

PLOT DATE: 6/24/2015
DRAWN BY: J. BLANCHARD
CHECKED K. KERN