DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
STOWE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	2.014	G	VR-017	24	30		LLL 24,000 LBS						1		X														
SB	1.997	G	VR-017	24	30		6/14	5.00								1		14.50 X									LUCE HILL RD (TH-5); INSTALL 100 FT FROM STOP		9	
SB	1.993	G	R1-1	30	30		STOP						1		X														
		G	R1-1	30	30		6/14	6.25								1		14.00 X									LUCE HILL RD (TH-5)	X		
SB	1.987	G	R1-1	30	30		STOP						1		X														
		G	R1-1	30	30		6/14	6.25								1		13.50 X									LUCE HILL RD (TH-5)	X		
SB	1.986	E/F	D3-1	UNK.	UNK.		LUCE HILL RD TH5						1		X														
		E/F	D3-1	50	12		6/14	4.17								2		21.50 X									LUCE HILL RD (TH-5)		11	
SB	1.981	G	R1-1	30	30		STOP						1		X														
		H	VD-700	6	10		MILE MARKER						1														SALVAGE AND MOUNT ON NEW POST BELOW STOP SIGN			
		G	R1-1	30	30		6/14	6.25								1		14.00 X									LUCE HILL RD (TH-5)	X		
SB	1.848	F	R2-1	24	30		SPEED LIMIT 30						1		X														
		F	R2-1	24	30		6/14	5.00								1		14.00 X										X		
SB	1.810	F	VW-622A	36	36		RECREATION TRAIL						1		X														
		F	W1-7	24	18		<===> DOUBLE ARROW						1																		
SIGN SUMMARY SHEET							SHEET TOTALS	32.92 SF	0.00 SF	0 EA	0 EA	0 EA	9 EA	0 EA	0 EA	7 EA		91.50 ~~105.0~~ FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB						
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	515.2	0.0	18	11	9	110	0	0	85		1275.0		0	0.0									

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **02 STOWE VT-108 SB TSS.xls** PLOT DATE: **6/24/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
STOWE SB SHEET 9 SHEET **37** OF **131**