DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CAMBRIDGE VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.000	C	VD-024	60	7.5		CAMBRIDGE/STOWE						1		2 X														
		C	VD-024	72	10		Cambridge | Stowe 6/10	5.00								2		23.25 X										6	
		C	VD-700	6	10		1080 0802 0000 / 1080 0808 0863 6/10	0.42																					T-44
		C	VD-700	6	10		6/10	0.42																					T-44
NB	0.152	A	W11-	30	30	FYG	5/25	6.25								1			16.50 X							INSTALL 800 FT NORTH OF TOWN LINE SIGN	X		
		A	W16-4P	30	24	FYG	TRIM NEXT 1500 FT 5/25	5.00																			X		
NB	0.199	A	W5-1	30	30		ROAD NARROWS 5/25						1		X														
		A	W5-1	36	36		TRIM ROAD NARROWS 5/25	9.00								2		29.50 X									X		
NB	0.247	A	W7-3aP	24	18		NEXT 2 MILES 5/25						1		X														
		A	W1-5R	30	30		RIGHT WINDING CURVES 5/25						1																
		A	W1-5R	30	30	FY	TRIM 5/25	6.25								1			14.25 X								X		
		A	W7-3aP	24	18	FY	NEXT 2 MILES 5/25	3.00																			X		
NB	0.287	A	W8-12	30	30		NO CENTER STRIPE TRIM 7/6 5/25						1		X														
		A	W8-12	36	36	FY	NO CENTER LINE 5/25	9.00								2		28.00 X									X		
NB	0.432	A	VW-285	30	30	FY	FALLING ROCK SYMBOL 5/25			1				X															
							SHEET TOTALS	44.33	0.00	1	0	0	5	0	2 ~~0~~	8		111.50 ~~120.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	611.0	0.0	29	13	10	140	0	0	110		1650.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STOWE - BERKSHIRE
PROJECT NUMBER: STPG SIGN (49)
FILE NAME: 03 CAMBRIDGE VT-108 NB TS
PLOT DATE: 4/15/2015
PROJECT MANAGER: D. BRYANT
DRAWN BY: J. BLANCHARD
DESIGNED BY: J. BLANCHARD
CHECKED: K. KERN
CAMBRIDGE NB SHEET 1
SHEET 45 OF 131