DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CAMBRIDGE VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	W7-3aP	24	18	FY	NEXT 1 MILE			1																			
NB	0.832	A	W11-2	30	30	FYG	PEDESTRIAN SYMBOL 5/25						1		X														
		A	W16-4P	24	18	FYG	NEXT 2000 FT 5/25						1																
		A	W11-2	30	30	FYG	TRIM 5/25	6.25								1			13.75 X						X		
		A	W16-4P	30	24	FYG	5/25	5.00																			X		
NB	1.052	A	W7-1	30	30		HILL SYMBOL TRIM 7/6 5/25						1		X														
		A	W7-2a	24	18		USE LOW GEAR 5/25						1																
		A	W7-1a	30	30	FY	TRIM 5/25	6.25								1		13.75 X						X		
		A	W7-3aP	24	18	FY	5/25	3.00																			X		
NB	1.544	A	R2-1	24	30		SPEED LIMIT 40 TRIM 7/6 5/25						1		X														
		A	R2-1	24	30		TRIM 5/25	5.00								1		12.25 X							REQUIRES VEGETATION CLEARING (SEE GENERAL NOTE 5 ON SHEET 2)	X		
NB	1.999	A	R2-1	24	30		SPEED LIMIT 40 5/25			1				X															
NB	2.128	A	W1-4R	36	36		RIGHT REVERSE CURVE 5/25						1		X														
		A	W13-1P	24	24		35 MPH TRIM 7/6 5/25						1																
		A	W1-4R	30	30		5/25	6.25								1		14.75 X							REQUIRES VEGETATION CLEARING (SEE GENERAL NOTE 5 ON SHEET 2)	X		
SIGN SUMMARY SHEET							SHEET TOTALS	31.75	0.00	2	0	0	7	0	0	4		54.50 ~~60.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	611.0	0.0	29	13	10	140	0	0	110		1650.0		0	0.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **03 CAMBRIDGE VT-108 NB TS** PLOT DATE: **4/15/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
CAMBRIDGE NB SHEET 2 SHEET **46** OF **131**