DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CAMBRIDGE VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	W16-9P	24	12	FYG	6/7	2.00																			X		
NB	8.863	A	S1-1	30	30	FYG	SCHOOL SYMBOL 6/7						1		X														
		A	W16-7P	24	12	FYG	DIAGONAL ARROW WARNING 6/7						1																
		A	S1-1	36	36	FYG	6/7	9.00								1			14.75 X							X		
		A	W16-7P	24	12	FYG	6/7	2.00																			X		
NB	8.869	A/B	D3-1	40	12		6/7	3.33								1		11.00 X									SCHOOL ST (TH-55); INSTALL 10 FT SOUTH OF UTILITY POLE		12	
NB	8.870	A/B	D3-1	UNK.	UNK.		SCHOOL ST 6/7						1		X														
		C/D	D3-1	UNK.	UNK.		MAIN ST 6/7						1																
NB	8.871	C	VR-017	24	30		LLL 24,000 LBS 6/7						1		X														
		D	R1-1	30	30		STOP 6/7						1																
		C	VD-700	6	10		MILE MARKER 6/7				1	1	1														SALVAGE AND MOUNT ON NEW POST BELOW STOP SIGN			
		D	R1-1	30	30		6/7	6.25								1		13.50 X									SCHOOL ST (TH-55)	X		
NB	8.871	C	R2-1	30	24		SPEED LIMIT 25 6/7				1	1	1		X												SCHOOL ST (TH-55); SALVAGE AND REMOUNT ON NEW POST BELOW LLL			
		C	VR-017	24	30		6/7	5.00								1			16.00 X								SCHOOL ST (TH-55)		9	
NB	8.928	A	W1-1L	30	30		LEFT TURN 6/7						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	27.58	0.00	0	2	2	9	0	0	4		~~60.0~~ 55.25		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	611.0	0.0	29	13	10	140	0	0	110		1650.0		0		0.0							

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **03 CAMBRIDGE VT-108 NB TS** PLOT DATE: **4/15/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
CAMBRIDGE NB SHEET 17 SHEET **61** OF **131**