DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CAMBRIDGE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	8.991	F	R2-1	24	30		SPEED LIMIT 25			1				X															
SB	8.942	F	S1-1	30	30	FYG	SCHOOL SYMBOL 5/9						1		X														
		F	W16-9P	24	12	FYG	AHEAD WARNING 5/9						1																
		F	S1-1	36	36	FYG	TRIM 5/9	9.00								1			14.00 X							REQUIRES VEGETATION CLEARING	X		
		F	W16-9P	24	12	FYG	5/9	2.00																				X		
SB	8.924	F	VW-207BP	24	18		BLIND PERSON 5/9						1		X														
		F	W11-2	30	30		PEDESTRIAN SYMBOL 5/9						1																
		F	W11-2	30	30	FYG	TRIM 5/9	6.25								1		15.25 X									X		
		F	W16-4P	24	18	FYG	5/9	3.00																				X		
SB	8.891	F	R2-1	24	30		SPEED LIMIT 25 5/9						1		X														
		F	R2-1	24	30		5/9	5.00								1			13.50 X									X		
SB	8.887	E/F	D3-1	UNK.	UNK		DEPOT ST 5/9						1		X														
		C/D	D3-1	32	12		5/9	2.67								1			11.00 X								DEPOT ST (TH-53); FIELD LOCATE FOR VISIBILITY FROM VT-108		12	
		E/F	D3-1	36	12		5/9	3.00																			DEPOT ST (TH-53)		12	
SB	8.887	G	VR-017	24	30		TRIM 5/9	5.00								1		14.00 X								DEPOT ST (TH-53); INSTALL IN LINE WITH SECOND CLUSTER OF TREES; REQUIRES VEGETATION CLEARING		9	
							SHEET TOTALS	35.92	0.00	1	0	0	6	0	0	5		~~67.75~~ ~~75.0~~		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	624.4	0.0	23	7	7	134	0	0	99		1485.0		2			324.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **04 CAMBRIDGE VT-108 SB TS**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **J. BLANCHARD**
PLOT DATE: **6/25/2015**
DRAWN BY: **J. BLANCHARD**
CHECKED **K. KERN**
CAMBRIDGE SB SHEET 1
SHEET **65** OF **131**