DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CAMBRIDGE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		G	M4-5	24	12		TO STATE 8/26						1																
		G	M1-5	30	24		VERMONT 109 8/26						1																
		G	M6-1	21	15		RIGHT ---> STATE 8/26						1																
		H	M3-3	24	12		SOUTH STATE 7/7						1																
		H	M1-5	30	24		VERMONT 108 7/7						1																
		H	M6-2	21	15		RIGHT ---> (45 DEG) STATE 7/7						1																
		G	M4-5	24	12	GRN/ WHT	8/16	2.00												2			29.0 X		2B	29.0 LF X 10.80 LB/LF =313.2 LBS	X		
		G	M3-4	24	12	GRN/ WHT	8/16	2.00																			X		
		G	M1-5	24	24	GRN/ WHT	8/16	4.00																					E-136B
		G	M6-2L	21	15	GRN/ WHT	8/16	2.19																			X		
		G	M4-5	24	12	GRN/ WHT	8/16	2.00																			X		
		G	M3-2	24	12	GRN/ WHT	8/16	2.00																			X		
		G	M1-5	24	24	GRN/ WHT	TRIM 7/7	4.00																					E-136B
		G	M6-1R	21	15	GRN/ WHT	7/7	2.19																			X		
		G	M3-1	24	12	GRN/ WHT	7/7	2.00																	2C		X		
							SHEET TOTALS	22.38	0.00	0	0	0	6	0	0	0		0.0		2	0.0	0.0	324.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	624.4	0.0	23	7	7	134	0	0	99		1485.0		2			~~324.0~~ 313.2						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STOWE - BERKSHIRE
PROJECT NUMBER: STPG SIGN (49)

FILE NAME: 04 CAMBRIDGE VT-108 SB TS
PROJECT MANAGER: D. BRYANT
DESIGNED BY: J. BLANCHARD
CAMBRIDGE SB SHEET 4

PLOT DATE: 6/25/2015
DRAWN BY: J. BLANCHARD
CHECKED: K. KERN
SHEET 68 OF 131