DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CAMBRIDGE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		G	M1-5	30	24	GRN/ WHT	7/7	5.00																					E-136B
		G	M6-1R	21	15	GRN/ WHT	7/7	2.19																			X		
		G	M4-5	24	12	GRN/ WHT	7/7	2.00																			X		
		G	M1-5	30	24	GRN/ WHT	8/26	5.00																					E-136B
		G	M6-1R	21	15	GRN/ WHT	8/26	2.19																			X		
		H	M3-3	24	12	GRN/ WHT	8/26	2.00																			X		
		H	M1-5	30	24	GRN/ WHT	8/26	5.00																					E-136B
		H	M6-2R	21	15	GRN/ WHT	8/26	2.19																			X		
SB	8.743	G	R1-1	30	30		STOP 5/9						1		X														
		G	R1-1	30	30		5/9	6.25								1		13.0 X								CHURCH ST; INSTALL ADJACENT TO PAVEMENT MARKINGS	X		
SB	8.741	F	R1-1	30	30		STOP 5/9						1		X														
		C/D	D3-1	32	12		5/9	2.67								1			13.0 X							CHURCH ST; MOUNT TO STREET NAME SIGN WITH BRACKET		12	
		E/F	D3-1	42	12		5/9	3.50																		CHURCH ST; MOUNT TO STOP SIGN WITH BRACKET		13	
		F	R1-1	30	30		5/9	6.25																		CHURCH ST	X		
SB	8.722	F	VW-133R	30	30		5/9	6.25								1		14.0 X								INSTALL AT END OF WOOD POST FENCE		10	
SIGN SUMMARY SHEET							SHEET TOTALS	50.48	0.00	0	0	0	2	0	0	3		~~45.0~~ 40.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	624.4	0.0	23	7	7	134	0	0	99		1485.0		2		324.0							

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**

FILE NAME: **04 CAMBRIDGE VT-108 SB TS** PLOT DATE: **6/25/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
CAMBRIDGE SB SHEET 5