DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CAMBRIDGE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	8.714	F	VW-054R	30	30		HIDDEN DRIVE RIGHT 5/9						1		X														
SB	8.692	F	R2-1	24	30		SPEED LIMIT 35 5/9						1		X														
		F	VR-041	30	30		THROUGH WAY BEGINS HERE 5/9						1																
		F	R2-1	24	30		TRIM 5/9	5.00								1		12.50 X								X		
SB	8.655	F	M3-3	24	12		SOUTH STATE 5/9						1		X														
		F	M1-5	30	24		VERMONT 108 5/9						1																
		F	W8-1	30	30		BUMP TRIM 5/9						1																
		F	M3-3	24	12	GRN/WHT	5/9	2.00								1		14.75 X								X		
		F	M1-5	30	24	GRN/WHT	5/9	5.00																				E-136B
SB	8.629	F	VW-060	30	30		HIDDEN DRIVES 5/9						1		X														
		F	VD-700	6	10		MILE MARKER 5/9				1	1	1														SALVAGE AND MOUNT ON NEW POST BELOW HIDDEN DRIVES SIGN			
		F	VW-060	30	30		5/9	6.25								1		14.00 X										10	
SB	8.555	F	VR-493H	48	60		VT 108 OPEN TO SKI AREA CLOSED THRU SMUGGLERS NOTCH (HINGED)			1				X																
SB	8.509	F	R2-1	24	30		SPEED LIMIT 35 5/9						1		X														
SB	8.451	F	W1-2R	30	30		RIGHT CURVE 5/9						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	18.25	0.00	1	1	1	10	0	0	3		~~45.0~~ 41.25		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	624.4	0.0	23	7	7	134	0	0	99		1485.0		2		324.0							

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **04 CAMBRIDGE VT-108 SB TS** PLOT DATE: **6/25/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
CAMBRIDGE SB SHEET 6 SHEET **70** OF **131**