DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CAMBRIDGE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W1-2R	30	30		5/9	6.25								1		13.75 X									X		
SB	8.408	F	S3-1	30	30		SCHOOL BUS STOP AHEAD 5/9						1		X														
		F	S3-1	36	36	FYG	TRIM 5/9	9.00								2		27.25 X									X		
SB	8.250	E	W1-2L	36	36		LEFT CURVE 5/9						1		X														
SB	8.190	E	R2-1	36	48		SPEED LIMIT 35 5/9						1		X														
		F	R2-1	24	30		SPEED LIMIT 40 5/9						1																
		F	R2-1	24	30		TRIM 5/9	5.00								1		14.00 X									X		
SB	8.112	F	VW-054R	30	30	FY	HIDDEN DRIVE RIGHT 5/11						1		X														
		F	VW-133R	30	30	FY	TRIM 5/11	6.25								1		14.00 X										10	
SB	8.007	F	R2-1	24	30		SPEED LIMIT 40 5/11						1		X														
SB	7.751	F	R2-1	24	30		NEED TO CHANGE TO 7.757 5/11 8/15 RELOCATED	5.00								1		15.00 X									INSTALL ACROSS FROM NB 40 MPH AT SAME MILEPOINT	X		
SB	7.606	F	W1-1L	30	30		LEFT TURN 5/11						1		X														
		F	W13-1P	24	24		30 MPH 5/11						1																
SB	7.564	F	W1-1L	30	30		TRIM 5/11	6.25								1			16.00 X								INSTALL 222 FT SOUTH OF EXISTING	X		
		F	W13-1P	18	18		5/11	2.25																				X	
SIGN SUMMARY SHEET							SHEET TOTALS	40.00	0.00	0	0	0	8	0	0	7		100.00 ~~105.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	624.4	0.0	23	7	7	134	0	0	99		1485.0		2	324.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **04 CAMBRIDGE VT-108 SB TS** PLOT DATE: **6/25/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
CAMBRIDGE SB SHEET 7 SHEET **71** OF **131**