DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CAMBRIDGE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN						2													"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	7.399	E	W1-6	48	24		RIGHT ===> LARGE ARROW						1		X													
SB	7.309	E	W1-1R	30	30		RIGHT TURN						1		X													
		E	W13-1P	24	24		30 MPH						1															
SB	7.264	E/F	D3-1	UNK.	UNK.		IRIS LANE 5/11						1		X													
		E/F	D3-1	40	12		Iris Ln PVT TRIM 5/11	3.33								1		11.25 X								IRIS LN (PVT)		13	
SB	7.226	E/F	D3-1	UNK.	UNK.		STEBBINS RD						1		X													
		G/H	D3-1	UNK.	UNK.		VT RTE 108						1															
		G	VD-700	6	10		MILE MARKER						1															
SB	7.226	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS TRIM 5/11	5.00								1		14.75 X								STEBBINS RD (TH-44); INSTALL 50 FT WEST OF UTILITY POLE		9	
SB	7.217	H	R1-1	30	30		STOP 5/11						1		X													
		G	VD-700	6	10		MILE MARKER 5/11				1	1	1													SALVAGE AND MOUNT ON NEW POST BELOW STOP SIGN			
		H	R1-1	30	30		STOP 5/11	6.25								1		14.00 X								STEBBINS RD (TH-44)	X		
SB	7.217	C/D	D3-1	52	12		VT Rte 108 S 5/11	4.33								2		25.00 X								STEBBINS RD (TH-44); FIELD LOCATE FOR VISIBILITY FROM VT-108		12	
		E/F	D3-1	50	12		Stebbins Rd 5/11	4.17																				13	
SB	6.880	E/F	D3-1	56	12		Holmes Dr PVT 6/30	4.67								2		20.75 X								HOLMES DR (PVT); FIELD LOCATE FOR VISIBILITY FROM VT-108		13	
SIGN SUMMARY SHEET							SHEET TOTALS	27.75	0.00	0	1	1	11 ~~9~~	0	0	7		85.75 ~~105.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	624.4	0.0	23	7	7	134	0	0	99		1485.0		2		324.0							

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **04 CAMBRIDGE VT-108 SB TS** PLOT DATE: **6/25/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED: **K. KERN**
CAMBRIDGE SB SHEET 10 SHEET **74** OF **131**