DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CAMBRIDGE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	VD-062M	72	16		BUSINESS SIGN 5/12			1																			
		F	VD-062M	72	16		BUSINESS SIGN 5/12			1																			
SB	4.056	F	VW-092	36	36		UNSAFE TO PASS 5/12						1		X														
		F	VW-092	36	36		5/12	9.00								2	28.75 X									10	
SB	4.032	G	VR-017	24	30		LLL 12,000 LBS 5/12						1		X														
		G	VR-017	24	30		5/12	5.00								1	13.50 X								DESJARDINS RD (TH-75)		9	
SB	4.027	H	R1-1	30	30		STOP 5/12						1		X														
		G	VD-700	6	10		MILE MARKER 5/12				1	1	1														SALVAGE AND MOUNT ON NEW POST BELOW STOP SIGN			
		H	R1-1	30	30		5/12	6.25								1	13.50 X								DESJARDINS RD (TH-75)	X		
SB	4.026	C/D	D3-1	UNK.	UNK.		VT RTE 108 S. 5/12						1		X														
		E/F	D3-1	UNK.	UNK.		DESJARDINS RD 5/12						1																
		E/F	D3-1	56	12		5/12	4.67								2	21.75 X								DESJARDINS RD (TH-75); FIELD LOCATE FOR VISIBILITY FROM VT-108		13	
SB	3.906	F	W11-2	30	30	FYG	PEDESTRIAN SYMBOL 5/12						1		X														
		F	W16-7P	24	12	FYG	DIAGONAL ARROW WARNING 5/12						1																
		F	W11-2	30	30	FYG	5/12	6.25								1	14.50 X									X		
SIGN SUMMARY SHEET							SHEET TOTALS	31.17	0.00	2	1	1	8	0	0	7	~~105.0~~ 92.00			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	624.4	0.0	23	7	7	134	0	0	99	1485.0			2	324.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **04 CAMBRIDGE VT-108 SB TS** PLOT DATE: **6/25/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
CAMBRIDGE SB SHEET 14 SHEET **78** OF **131**