DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BAKERSFIELD VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		C	M6-1	21	15		RIGHT ---> STATE 6/30						1																
		C	M3-1	24	12	GRN/WHT	6/30	2.00								2		31.25 X							2C		X		
		C	M1-5	30	24	GRN/WHT	6/30	5.00																				E-136B
		C	M6-1L	21	15	GRN/WHT	6/30	2.19																			X		
		C	M3-3	24	12	GRN/WHT	6/30	2.00																			X		
		C	M1-5	30	24	GRN/WHT	6/30	5.00																				E-136B
		C	M6-1R	21	15	GRN/WHT	6/30	2.19																			X		
NB	3.695	D	R1-1	30	30		STOP 5/4						1		X														
		A/B	D3-1	UNK.	UNK.		E BAKERSFIELD RD TH 2 5/4						1																
		C	VD-700	6	10		MILE MARKER 5/4				1	1	1														SALVAGE AND MOUNT ON NEW POST BELOW STOP SIGN			
		D	R1-1	30	30		STOP 5/4	6.25								1		13.50 X								E BAKERSFIELD RD (TH-2)	X		
NB	3.695	A/B	D3-1	66	12		E Bakersfield Rd 5/4	5.50								2		22.00 X								E BAKERSFIELD RD (TH-2); INSTALL 10 FT CLOSER TO VT 108 THAN STOP SIGN		13	
NB	3.706	C	UNK.	UNK.	UNK.		NO DOGS, HORSES, OR ATVS's			1				X															
NB	3.737	A	S1-1	36	36	FYG	SCHOOL SYMBOL 5/4						1		X														
		A	W16-9P	30	18	FYG	AHEAD WARNING 5/4						1																
SIGN SUMMARY SHEET							SHEET TOTALS	30.13	0.00	1	1	1	6	0	0	5		66.75 ~~75.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	191.4	0.0	6	4	4	48	0	0	30		450.0		0	0.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **05 BAKERSFIELD VT-108 NB T** PLOT DATE: **4/15/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
BAKERSFIELD NB SHEET 3 SHEET **87** OF **131**