DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BAKERSFIELD VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		C	VR-017	24	30		LLL 24,000 LBS 5/5						1																
		C	VD-700	6	10		MILE MARKER 5/5						1																
NB	7.983	A/B	D3-1	34	12		5/5	2.83								1		14.75 X								OVITT RD (TH-42); MOUNT TO STOP SIGN WITH BRACKET		13	
		D	R1-1	30	30		5/5	6.25																		OVITT RD (TH-42); INSTALL 37 FT NORTH OF EXISTING	X		
NB	7.998	A	W11-4	30	30		CATTLE SYMBOL 5/5						1		X														
		A	W11-4	30	30		5/5	6.25								1		15.50 X									X		

SIGN SUMMARY SHEET	SHEET TOTALS	15.33	0.00	0	0	0	3	0	0	2	30.25 ~~30.0~~		0	0.0	0.0	0.0	0.0												
		SF	SF	EA	EA	EA	EA	EA	EA	EA	FT		EA	LB	LB	LB	LB												
VERMONT AGENCY OF TRANSPORTATION	TOWN DIRECTIONAL TOTALS	191.4	0.0	6	4	4	48	0	0	30	450.0		0	0.0															

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **05 BAKERSFIELD VT-108 NB T** PLOT DATE: **4/15/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
BAKERSFIELD NB SHEET 7 SHEET **91** OF **131**