DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BAKERSFIELD VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	M1-5	30	24		VERMONT 108						1																
		F	M3-3	24	12	GRN/WHT	TRIM 5/5	2.00								1		14.50 X									X		
		F	M1-5	30	24	GRN/WHT	5/5	5.00																					E-136B
SB	4.584	F	VR2-5A	24	30		REDUCED SPEED AHEAD 5/5						1		X														
SB	4.551	G	VR-017	24	30		LLL 24,000 LBS 5/5					1				1		X									HYDES HILL RD (TH-23); INSTALL SALVAGED SIGN IN NEW LOCATION			
		H	R1-1	30	30		STOP 5/5						1																
SB	4.551	G	W14-1	30	30		DEAD END 5/5					1				1		13.50 X									HYDES HILL RD (TH-23); INSTALL WEST OF LLL			
SB	4.548	G	VR-017	24	30		LLL 24,000 LBS 5/5				1		1		X			14.00									SALVAGE TO NEW LOCATION			
SB	4.548	H	R1-1	30	30		TRIM 5/5	6.25								1		14.25 X									HYDES HILL RD (TH-23)	X		
SB	4.548	E/F	D3-1	UNK.	UNK.		HYDES HILL RD 5/5						1		X														
		G	W14-1	30	30		DEAD END 5/5				0 ~~1~~		1														SALVAGE TO NEW LOCATION			
		E/F	D3-1	56	12		5/5	4.67								2		22.00 X									HYDES HILL RD (TH-23); FIELD LOCATE FOR VISIBILITY FROM VT-108		13	
SB	4.516	F	W3-5	36	36		5/5	9.00								2		28.50 X									INSTALL 168 FT SOUTH OF HYDES HILL RD (TH-23) STREET SIGN	X		
SB	4.421	F	R2-1	24	30		SPEED LIMIT 40 5/5						1		X														
		F	R2-1	30	36		TRIM 5/5	7.50								1		13.50 X									REQUIRES VEGETATION CLEARING	X		
SIGN SUMMARY SHEET							SHEET TOTALS	34.42	0.00	0	~~1~~ 2	2	7	0	0	9		~~135.0~~ 120.25		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	235.0	0.0	6	11	11	58	0	0	43		645.0		0	0.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **06 BAKERSFIELD VT-108 SB T** PLOT DATE: **6/25/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
BAKERSFIELD SB SHEET 3 SHEET **94** OF **131**